



**QUALITY MANAGEMENT PROCESSES THROUGH THE
INTEGRATION OF BIM APPROACH WITH MODULAR
CONSTRUCTION SYSTEMS**

İlayda OMURTAY

**IN PARTIAL FULFILLMENT OF THE REQUIREMENTS
FOR THE DEGREE OF MASTER OF SCIENCE
IN ARCHITECTURE DEPARTMENT**

**GAZİ UNIVERSITY
GRADUATE SCHOOL OF NATURAL AND APPLIED SCIENCES**

JANUARY 2024

ETHICAL STATEMENT

I at this moment declare that in this thesis study, I prepared the thesis writing rules of Gazi University Graduate School of Natural and Applied Sciences;

- All data, information, and documents presented in this thesis have been obtained within the scope of academic rules and ethical conduct,
 - All information, documents, assessments, and results have been presented by scientific ethical conduct and moral rules,
 - All material used in this thesis that is not original to this work has been exhaustively cited and referenced,
 - No change has been made in the data used,
 - The work presented in this thesis is original,
- or else, I admit all loss of rights to be incurred against me.

İlayda OMURTAY

31/01/2024

QUALITY MANAGEMENT PROCESSES THROUGH THE INTEGRATION OF BIM APPROACH WITH MODULAR CONSTRUCTION SYSTEMS

(M.Sc. Thesis)

İlayda OMURTAY

GAZİ UNIVERSITY

GRADUATE SCHOOL OF NATURAL AND APPLIED SCIENCES

January 2024

ABSTRACT

Today's construction industry is undergoing a profound transformation driven by advancing technologies and methodologies. At the forefront of this evolution lies Building Information Modeling (BIM), a pivotal tool shaping the planning, design, production, and management phases of construction projects. With a growing emphasis on efficiency and speed, modern and modular construction systems have emerged as compelling options for firms seeking streamlined project execution. This study aims to explore the integration of modular construction systems with BIM technology and assess its impact on project management and quality control processes. Within this research scope, fundamental concepts of BIM technology and modular construction methodologies are meticulously examined. Furthermore, the study delves into the potential synergies between BIM and modular construction systems in enhancing project management and ensuring quality outcomes. Drawing insights from the Scopus database, the study conducts a comprehensive review of the existing literature on building information modeling (BIM), employing bibliometric and systematic literature review methods. Through meticulous analysis and examination of the gathered articles, the study addresses the question of how the principles of the PDCA (Plan-Do-Check-Act) cycle are employed to complete the quality management cycle. Despite the wealth of research in this area, there remains a notable gap in the literature regarding concrete evidence of the efficacy of this integration in improving project quality. As a result, this thesis underscores the potential benefits of integrating modern and modular construction systems with BIM technology for project management and quality assurance. However, it also highlights the need for further research to delve deeper into the implementation of this integration across diverse construction projects.

Science Code : 80115

Key Words: : Building information modeling (BIM), Modular construction,
Quality in Project Management

Page Number : 115

Supervisor : Prof. Dr. Ali İhsan ÜNAY,

Co-Supervisor : Assoc. Prof. Dr. Asena SOYLUK

YBM YAKLAŞIMININ MODÜLER İNŞAAT SİSTEMLERİYLE ENTEGRASYONU YOLUYLA KALİTE YÖNETİM SÜREÇLERİ

(Yüksek Lisans Tezi)

İlayda OMURTAY

GAZİ ÜNİVERSİTESİ
FEN BİLİMLERİ ENSTİTÜSÜ

Ocak 2024

ÖZET

Günümüz inşaat sektörü, gelişen teknoloji ve metodolojilerin etkisiyle derin bir dönüşüm yaşıyor. Bu evrimin ön saflarında inşaat projelerinin planlama, tasarım, üretim ve yönetim aşamalarını şekillendiren önemli bir araç olan Yapı Bilgi Modellemesi (BIM) yer alıyor. Verimlilik ve hıza verilen önemin giderek artmasıyla birlikte, modern ve modüler inşaat sistemleri, proje uygulamasını kolaylaştırmak isteyen firmalar için cazip seçenekler olarak ortaya çıkmıştır. Bu çalışma, modüler inşaat sistemlerinin BIM teknolojisiyle entegrasyonunu araştırmayı ve bunun proje yönetimi ve kalite kontrol süreçleri üzerindeki etkisini değerlendirmeyi amaçlamaktadır. Bu araştırma kapsamında BIM teknolojisinin temel kavramları ve modüler inşaat metodolojileri titizlikle incelenmektedir. Ayrıca çalışma, proje yönetimini geliştirme ve kaliteli sonuçlar sağlama konusunda BIM ile modüler inşaat sistemleri arasındaki potansiyel sinerjiyi de araştırıyor. Scopus veri tabanından içgörüler elde eden çalışma, bibliyometrik ve sistematik literatür tarama yöntemlerini kullanarak bina bilgi modellemesi (BIM) hakkındaki mevcut literatürün kapsamlı bir incelemesini gerçekleştiriyor. Toplanan makalelerin titiz bir şekilde analiz edilmesi ve incelenmesi yoluyla çalışma, kalite yönetimi döngüsünü tamamlamak için PDCA (Planla-Uygula-Kontrol Et-Önlem Al) döngüsünün ilkelerinin nasıl kullanıldığı sorusunu ele alıyor. Bu alandaki araştırmaların zenginliğine rağmen, literatürde bu entegrasyonun proje kalitesinin iyileştirilmesindeki etkinliğinin somut kanıtlarına ilişkin dikkate değer bir boşluk bulunmaktadır. Sonuç olarak bu tez, proje yönetimi ve kalite güvencesi için modern ve modüler inşaat sistemlerini BIM teknolojisiyle entegre etmenin potansiyel faydalarının altını çiziyor. Bununla birlikte, bu entegrasyonun çeşitli inşaat projelerinde daha derinlemesine uygulanmasına yönelik daha fazla araştırmaya duyulan ihtiyacın da altını çiziyor.

Bilim Kodu : 80115

Anahtar Kelimeler : Bina bilgi modelleme (BIM), Modüler inşaat, Proje Yönetiminde Kalite

Sayfa Adedi : 115

Danışman : Prof. Dr. Ali İhsan ÜNAY

İkinci Danışman : Doç. Dr. Asena SOYLUK

ACKNOWLEDGEMENTS

First, I would like to express my endless gratitude to my valuable advisors, Prof. Dr. Ali İhsan ÜNAY and Assoc. Prof. Asena SOYLUK, enlightened me with their knowledge and supported me throughout my thesis work. I am also deeply grateful to express my gratitude to my mother, Burcu OMURTAY, and my father, Bora OMURTAY, who supported me under all circumstances throughout my life, and to my grandmother, Sevgi YAVUZ, who always supported me with her prayers. Further, I want to offer my special thanks to Yener YILDIRIM and Banu YILDIRIM from the construction industry for their contributions. Lastly, I would like to thank my colleague Mehmet Adnan İLBAY, who guided me with his experiences.

CONTENTS

	Page
ABSTRACT	iv
ÖZET	v
ACKNOWLEDGEMENTS	vi
CONTENTS	vii
LIST OF TABLES	x
LIST OF FIGURES	xi
SYMBOLS AND ABBREVIATIONS	xii
1. INTRODUCTION	1
2. LITERATURE REVIEW	7
2.1. BIM and Modern Construction Systems: Definitions and Characteristics	9
2.1.1. Fundamental concepts of BIM technology	10
2.1.2. Characteristics of modern construction systems	13
2.2. BIM and Modular Construction Systems: Integration Opportunities	16
2.2.1. Advantages and limitations of modular construction	16
2.2.2. Potential alignment of BIM and modular construction systems	17
2.3. Integration of BIM with Project Management and Quality Management	18
2.3.1. Relationship between BIM and project management	18
2.3.2. Challenges and considerations in BIM and project management integration	20
2.4. Utilization of Integrated BIM and Modular Construction Approach in the Design Phase	21
2.4.1. Modular design approach and integration with BIM	21
2.4.2. Enhancements in design efficiency and collaboration	24
2.4.3. Analysis and optimization of modular design through BIM	26

	Page
2.5. Integration of Modular Construction in Production and Assembly Phases	30
2.5.1. Utilization of BIM in production and assembly processes	31
2.5.2. Influence of BIM on material and resource management in modular production	33
2.5.3. Impact of BIM on error reduction and labor optimization in the assembly phase	36
2.6. Contribution of BIM and Modular Construction Integration to Quality Management and Monitoring	39
2.6.1. Quality control processes in modular production	42
2.6.2. BIM-based monitoring and quality assurance	43
2.6.3. Enhancements in quality and performance within modular construction systems	44
2.7. Impact of Project Management and BIM-MPS Integration on Project Success	44
2.7.1. Benefits of project management and BIM integration	44
2.7.2. Influence of BIM-MPS integration on project planning and monitoring	45
2.7.3. Integration of risk management and decision-making processes through BIM-MPS	46
3. RESEARCH METHOD AND MATERIAL	47
3.1. Bibliometric Analysis	50
3.2. Systematic Review Analysis	53
3.3. Enhancing Modular Construction Quality through BIM: Hypotheses	54
3.3.1. Hypothesis 1: Improved efficiency and reduced delays	55
3.3.2. Hypothesis 2: Expenditure control and logistics management	57
3.3.3. Hypothesis 3: Enhanced communication and information management	58
3.3.4. Hypothesis 4: Holistic approach throughout the construction life cycle	59

	Page
3.3.5. Hypothesis 5: Enhanced collaboration and stakeholder engagement	61
3.3.6. Hypothesis 6: Improved quality through cost management	62
3.4. Continuous Improvement in Construction Quality: Validating the Impact of BIM through the PDCA Cycle	66
4. CONCLUSION	93
4.1. Discussion of Enhancing Modular Construction Quality through BIM	95
4.2. Future Research Areas	97
REFERENCES	101
CURRICULUM VITAE	115

LIST OF TABLES

Table	Page
Table 3.1. Article table based on the ‘Improved Efficiency and Reduced Delays’ hypothesis	56
Table 3.2. Article table based on the ‘Expenditure Control and Logistics Management’ hypothesis	58
Table 3.3. Article table based on the ‘Enhanced Communication and Information Management’ hypothesis	59
Table 3.4. Article table based on the ‘Holistic Approach throughout the Construction Life Cycle’ hypothesis	60
Table 3.5. Article table based on the ‘Enhanced collaboration and stakeholder engagement’ hypothesis	61
Table 3.6. Article table based on the ‘Improved quality through cost management’ hypothesis	63
Table 3.7. Table of 19 articles by PDCA assessment	69
Table 3.8. Table consisting of 19 articles according to common results from the PDCA evaluation	90

LIST OF FIGURES

Figure	Page
Figure 1.1. Flow diagram of the thesis	6
Figure 2.1. Modular construction – from manufacturing to site installation	14
Figure 2.2. Process map of BIM-enabled computerized design and fabrication of industrialized buildings with applications to modular housings	37
Figure 3.1. Flow diagram of the search methodology	49
Figure 3.2. Graph of 46 articles written between 2006-2023 for BIM, MCS and quality by year.....	51
Figure 3.3. Chart of 46 articles written between 2006-2023 for BIM, MCS and quality by country	51
Figure 3.4. Analysis of 46 articles written between 2006-2023 for BIM, MCS and quality according to keywords made in VOSviewer	52
Figure 3.5. Ishikawa diagram showing that the use of modular construction with BIM increases the quality	55
Figure 3.6. Numerical graph according to hypotheses	64
Figure 3.7. Year distribution graph according to hypotheses	65
Figure 3.8. Country distribution graph according to hypotheses.....	66
Figure 3.9. PDCA Cycle	67
Figure 3.10. Graph of 19 articles according to PDCA stages.....	76

SYMBOLS AND ABBREVIATIONS

The symbols and abbreviations used in this study are presented below, along with their explanations.

Abbreviations	Explanations
2D	two-dimensional space
3D	three-dimensional space
BIM	Building Information Modeling
MCS	Modular Construction Systems
SLR	Systematic Literature Review
HVAC	Heating, Ventilation, and Air Conditioning
MPS	Modular Project Scheduling
PDCA	Plan-Do-Check-Act
IOP	Internet of Protocol
IOT	Internet of Things
BbCN	BIM-based Construction Network

1. INTRODUCTION

Research question and purpose

In today's rapidly evolving construction industry, influenced by swift technological advancements and changing work methodologies, a significant transformation is underway. At the heart of this transformation lies Building Information Modeling (BIM), a technology that fundamentally reshapes the management, design, and implementation of construction projects. Simultaneously, modern construction approaches have gained prominence, aiming to achieve swift and efficient project completion, with modular construction systems taking a prominent position. This thesis work has been conducted under the title "Quality Management Processes Through the Integration of BIM Approach with Modular Construction Systems" with the aim of examining the effects of integrating modern construction systems with BIM technology on project management and quality management processes.

The fundamental question of this research is: How does the integration of modern and modular construction systems with BIM technology contribute to project management and quality management processes? Within the framework of this fundamental question, the main objective of the research is to investigate how the integration of modular construction systems with BIM technology makes a difference in the management and quality of construction projects, and to evaluate the potential advantages and challenges of this integration.

Derived from bibliometric and systematic analyses of 19 articles sourced from the Scopus database, this study formulates six hypotheses regarding the capacity of BIM to augment quality in modular construction. To sharpen the study's focus and comprehend its objectives better, underlying primary inquiries have been identified for each hypothesis. Therefore, for each hypothesis, a sub-research question has been formulated. These questions will aid in gaining a deeper understanding of the impact of BIM and modular construction on quality and will assist in achieving the overarching aim of the study. These sub-research questions will be utilized to delve into further detail in the structural and analytical sections of the study. Below are the hypotheses and questions.

Hypothesis 1: Improved efficiency and reduced delays

Sub-Research Question: What is the effect of BIM usage in modular construction on improving efficiency and reducing delays?

Hypothesis 2: Expenditure control and logistics management

Sub-Research Question: How does the utilization of BIM in modular construction projects affect expenditure control and logistics management?

Hypothesis 3: Enhanced communication and information management

Sub-Research Question: How does the implementation of BIM in modular construction enhance communication and information management?

Hypothesis 4: Holistic approach throughout the construction life cycle

Sub-Research Question: Should the integration of BIM and modular construction be studied for promoting a holistic approach throughout the construction life cycle?

Hypothesis 5: Enhanced collaboration and stakeholder engagement

Sub-Research Question: What is the significance of collaboration and stakeholder engagement in BIM and modular construction projects?

Hypothesis 6: Improved quality through cost management

Sub-Research Question: How can the impact of BIM usage on cost management be measured?

Additionally, the research went deeper by subjecting the identified articles to analysis through the PDCA (Plan-Do-Check-Act) cycle, in addition to formulating hypotheses based on information obtained from the Scopus database. This systematic review aimed to evaluate the completeness and effectiveness of quality management processes outlined in

the literature. Conducted in accordance with these objectives and sub-objectives, this thesis work aims to shed light on how the integration of BIM technology with modern construction approaches enables the creation of more efficient and effective projects, shaping the future of the construction industry. The findings of this thesis will provide essential guidance to stakeholders and researchers on how to seamlessly integrate BIM technology with modern construction approaches.

Through meticulous examination, this research seeks to render visible the transformative potential that resides within the convergence of BIM and contemporary construction practices. It endeavors to shed a clarifying light on the ways in which BIM can be harnessed as a catalyst for innovation, efficiency, and qualitative advancement throughout the construction industry. By meticulously scrutinizing the multifaceted facets of this integration, this study aspires to contribute a profound and enduring impact upon the construction domain, serving as a lighthouse that guides practitioners, policymakers, and academia toward a future characterized by more sustainable, cost-efficient, and qualitatively superior construction practices.

In this expansive endeavor, the research traverses an intricate landscape, delving into the intricacies of BIM, the dynamics of modern construction systems, the nuances of modular construction, and the intricate web of interrelationships among these elements. Through this journey, it aspires to paint a comprehensive portrait of the potential transformations and innovations that can be realized through the integration of BIM with contemporary construction systems, ultimately offering a panoramic view of a construction industry poised to meet the challenges and opportunities of the 21st century.

Significance of the study

In the present day, the construction industry is undergoing a significant evolution driven by rapid technological advancements and changing customer demands. At the center of this evolution is the rising importance of Building Information Modeling (BIM) technology. BIM offers an integrated approach to efficiently manage, design, and implement construction projects. Especially in large and complex projects, BIM technology enhances collaboration, data sharing, and management, ultimately reducing costs, shortening timelines, and improving quality.

However, this transformation in the construction sector is not solely limited to BIM technology. Modern construction approaches have also gained considerable popularity. These approaches aim to complete projects swiftly and efficiently, optimizing resource utilization and designing projects that align with sustainability principles. Modular construction systems, in particular, stand out as an approach where pre-manufactured modules are assembled to create structures. This approach accelerates the construction process while also offering advantages such as reduced waste production and enhanced energy efficiency.

This thesis work, conducted under the title "Quality Management Processes Through the Integration of BIM Approach with Modular Construction Systems" explores the potential benefits created in the construction sector through the integration of modern construction approaches with BIM technology. The significance of this research is focused on two main aspects:

Firstly, considering the complexity and cost of construction projects, the development of a more efficient and effective approach to project planning, construction, and management is of critical importance for the future of the sector. This thesis presents a significant research opportunity to understand how the integration of modern construction systems with BIM technology optimizes project processes and contributes to achieving better project outcomes.

Secondly, designing and implementing construction projects in line with sustainability and quality standards are gaining increasing importance. The fusion of BIM technology and modern construction approaches can play a pivotal role in achieving goals such as improved energy efficiency, reduced waste production, and higher construction quality. Through illuminating how integrated BIM and modern construction systems contribute to sustainability and quality management, this research can assist the sector in progressing towards these objectives.

In conclusion, the thesis titled "Quality Management Processes Through the Integration of BIM Approach with Modular Construction Systems" explains the significance of the research by demonstrating how the amalgamation of modern construction systems with BIM technology can aid the construction industry in producing projects that are more

efficient, sustainable, and of higher quality. The findings of this thesis will assist relevant stakeholders and researchers in gaining a better understanding of the positive impacts of integrating modern construction systems with BIM technology on the future of the sector.

The significance of this research study is underscored by its potential to catalyze transformative changes within the construction industry, offering a beacon of guidance and innovation to various stakeholders including practitioners, policymakers, and the academic community.

Method of research

This study delves into an exploration of the current landscape and future trajectories within the realm of Building Information Modeling (BIM) by drawing insights from the Scopus database. Employing a comprehensive approach, the investigation combines bibliometric and systematic literature review (SLR) methodologies, leveraging co-occurrence and co-citation analyses. Initially, 343 academic documents were meticulously sourced from the Scopus database, and subsequent analyses involved scrutinizing pertinent keywords and employing network visualization to unravel patterns in research interconnections.

Within this expansive dataset, a notable subset of 229 documents emerged after focusing solely on those relevant to construction projects. Further refinement identified 179 documents specifically related to BIM and modular construction. A more focused examination, encapsulated in 46 articles, underscored the argument that the integration of BIM into modular construction systems within the construction industry serves to enhance quality. A more focused review from this pool led to the selection of 19 of the 46 articles that formed the basis of analysis in this study. This assertion, in turn, advocates for the imperative of further exploration in this domain to augment the likelihood of successful outcomes in information modeling projects within the construction landscape (Figure 1.1).

It is noteworthy to mention that this review exclusively concentrates on academic documents gleaned from the Scopus database, thereby delineating the scope of the literature under scrutiny to topics specific to building information modeling, modular construction, and quality considerations.

In addition, this study goes beyond by delving into the hypotheses generated from the analysis of 19 selected articles. These hypotheses were scrutinized through the PDCA (Plan-Do-Check-Act) cycle, revealing insights into the enhancement of quality despite the limited existing studies in this domain. Recommendations were then put forth based on the constructed quality cycle, contributing to the advancement of research in the integration of BIM and modular construction for improved quality outcomes. This multifaceted approach reinforces the significance of further exploration and development in this evolving field.

In essence, this study contributes to the broader understanding of BIM's impact on modular construction, laying the foundation for future research initiatives and emphasizing the importance of ongoing exploration in this evolving field. The identified patterns, insights, and recommendations collectively underscore the potential for BIM to play a pivotal role in shaping the future landscape of quality improvement within the construction industry.




Figure 1.1. Flow diagram of the thesis

2. LITERATURE REVIEW

In contemporary construction landscapes, the demand for sustainable, cost-efficient, and high-quality construction practices has surged to the forefront. This heightened demand stems from the growing recognition of the construction sector's pivotal role in addressing global challenges, including urbanization, resource scarcity, and environmental sustainability [1]. Within this dynamic context, the integration of Building Information Modeling (BIM) technology with modern construction systems, particularly modular construction, emerges as a timely and imperative subject of exploration.

At the core of this study lies the aspiration to address pressing industry needs by providing comprehensive insights into the potential synergies and benefits of integrating BIM with modular construction. As construction projects grow in complexity and scale, the need for innovative solutions becomes increasingly pronounced. The integration of BIM technology is positioned as a pivotal solution to meet these evolving needs.

The research study's significance is multifaceted, spanning several key dimensions:

Enhanced construction practices

The findings and insights generated by this research are poised to influence construction practices profoundly. By illuminating the potential advantages and challenges of integrating BIM with modular construction, this study offers a roadmap for practitioners to enhance their project delivery methods [2,3].

Cost savings

The cost efficiency that can be realized through BIM integration holds significant financial implications for the construction industry. This study's significance is underscored by its potential to unveil opportunities for cost savings, whether through reduced project timelines, minimized rework, or optimized resource allocation [4,5,6].

Timely project delivery

As the construction sector grapples with the need for timely project delivery, the integration of BIM with modular construction offers a means to streamline processes and shorten project durations [7,8]. By addressing this critical issue, this research holds significant promise in enhancing overall project efficiency.

Quality assurance

Quality management is a non-negotiable aspect of construction projects, and this study's significance lies in its potential to elevate quality standards. Through BIM's capabilities in real-time inspection and verification, it becomes possible to minimize defects and errors, ultimately improving construction quality [9,10].

Environmental sustainability

In an era marked by a growing emphasis on sustainability, this research's significance extends to its potential to align construction practices with environmental objectives. By optimizing resource utilization and minimizing waste, BIM integration within modular construction can contribute to more sustainable building processes [11].

Academic advancement

Within the academic realm, this research offers a foundation for further inquiry and exploration. Its significance is underlined by its potential to inspire future research endeavors, enabling a deeper understanding of the evolving dynamics within the construction industry [12].

In summation, the significance of this research study resides in its capacity to transcend the boundaries of the theoretical and practical realms, offering tangible benefits and innovative pathways to stakeholders in the construction industry. By addressing the pressing needs and challenges of the construction sector, this study aspires to serve as a cornerstone for constructive change and progress within the industry, positioning itself as a lodestar

guiding the industry toward a future characterized by enhanced efficiency, sustainability, and quality [13].

This study delves into the integration of Building Information Modeling (BIM) with modern construction systems, representing a significant paradigm shift in the industry. It provides a comprehensive review of existing literature, examining fundamental concepts of BIM technology, characteristics of modern construction systems, the advantages and limitations of modular construction, and the potential synergy between BIM and modular construction systems.

2.1. BIM and Modern Construction Systems: Definitions and Characteristics

Building Information Modeling (BIM) and modern construction systems represent two integral components of contemporary construction practices. This section provides a comprehensive overview of both BIM technology and the essential characteristics defining modern construction systems, setting the foundation for understanding their integration.

Building Information Modeling (BIM) emerges as one of the most distinct reflections of digital transformation in the construction sector. BIM presents a data-driven approach encompassing the entire lifecycle of buildings from design to operation. On the other hand, modern construction systems can be defined as innovative and integrated approaches that go beyond traditional methods, offering features such as rapid production, flexibility, sustainability, and cost-effectiveness. This literature review explores the definitions and characteristics of BIM and modern construction systems while discussing the impact of their convergence on the construction sector.

Building Information Modeling (BIM) is a technology that offers a data-driven approach in various stages of construction projects, ranging from design to operation [14]. Going beyond 3D modeling, BIM integrates all project data. These data can go beyond geometric information and include parameters such as time, cost, materials, and energy. BIM enhances data sharing and collaboration among all stakeholders, reducing errors and unnecessary costs [15]. The utilization of BIM enables rapid decision-making during the construction phase, early detection of clashes, and data-driven decision-making during the operation phase [16].

The core concepts of BIM establish the foundation for a more effective, data-focused, and collaborative approach within the construction sector [17]. These concepts contribute to better project planning, reduced errors, improved communication, and efficient management throughout a project's entire lifecycle [18]. BIM's fundamental concepts enable the realization of more sustainable and innovative projects within the construction industry [19].

Modern construction systems, on the other hand, go beyond traditional construction methods and offer innovative and integrated structures that highlight characteristics such as rapid production, flexibility, sustainability, and cost-effectiveness [20]. Concepts like modular construction, prefabrication, and premanufacturing form the foundation of modern construction systems. Modular construction involves manufacturing building elements in factories and assembling them on-site, shortening construction time while improving quality control and reducing waste [21]. Prefabrication refers to the assembly of buildings using pre-manufactured components. This method significantly reduces construction time and can enhance design flexibility [22].

The combination of BIM and modern construction systems enables more effective and efficient management of construction projects. BIM's data-driven approach can facilitate the integration of modular or prefabricated elements during design, production, and assembly stages. Additionally, it can enhance communication and collaboration among project stakeholders, leading to reduced errors and costs.

In conclusion, BIM and modern construction systems are representatives of digitization and innovative approaches in the construction sector. The convergence of these two concepts can facilitate more effective, efficient, sustainable, and cost-effective management of construction projects. With further integration of BIM and modern construction systems in the future, significant transformations and improvements are anticipated in the construction sector.

2.1.1. Fundamental concepts of BIM technology

Building Information Modeling (BIM) represents a transformative technological innovation within the construction industry. At its core, BIM is a digital approach to

design, construction, and project management that involves creating and managing a three-dimensional digital representation of a building's physical and functional characteristics [23]. This digital model serves as a comprehensive repository of information, encompassing not only the building's geometric attributes but also data related to materials, systems, performance, and more [24].

BIM's core principles encompass object-based modeling, parametric design, and data interoperability [25,26]. Object-based modeling involves creating intelligent, data-rich building components that can be interacted with and analyzed throughout a project's lifecycle [27,28]. Parametric design allows for the establishment of relationships and constraints among components, ensuring that changes are propagated throughout the model [29,30]. Data interoperability ensures that BIM models can seamlessly exchange information with various software applications, fostering collaboration among project stakeholders [31,32].

One of BIM's distinguishing features is its capacity to facilitate real-time collaboration among multidisciplinary project teams. It promotes clash detection, where potential conflicts in design are identified and resolved before construction begins [33,34]. This proactive approach minimizes costly rework and errors, enhancing project efficiency [33,34].

The fundamental concepts of BIM technology are underpinned by several key principles:

Object-based modeling

BIM models are constructed using intelligent, parametric objects that represent various building elements (e.g., walls, doors, HVAC systems). These objects contain rich data attributes that define their properties, behavior, and interactions. This object-based modeling approach allows for the creation of a highly detailed and interconnected digital representation [35].

Parametric design

BIM models incorporate parametric design principles, enabling dynamic relationships between model elements. Changes made to one part of the model can trigger automatic adjustments throughout the entire design. This parametric capability ensures consistency and accuracy across the project [35].

Data interoperability

BIM promotes the seamless exchange of information among different software applications and project stakeholders. It leverages open standards and data formats, allowing architects, engineers, contractors, and facility managers to collaborate effectively [36].

Visualization

BIM provides powerful visualization tools that enable stakeholders to view and interact with the digital model in three dimensions. This aids in design communication, design validation, and clash detection [37].

Lifecycle integration

BIM is not limited to the design phase but extends throughout the entire building lifecycle, from concept and design to construction, operation, and maintenance. This holistic approach enhances project continuity and efficiency [38].

The adoption of BIM technology has revolutionized the construction industry by offering enhanced collaboration, improved decision-making, and increased project efficiency. Its ability to centralize and integrate project data and processes has made it an indispensable tool in modern construction practices.

2.1.2. Characteristics of modern construction systems

Modern construction systems are developed and widespread building technologies that provide alternatives to traditional construction methods. These systems are notable for their potential to offer faster construction processes, lower costs, and generally higher building quality. This literature review aims to discuss the characteristics of modern construction systems and their contributions to the construction industry.

The characteristics of modern construction systems can vary in different applications and projects. However, there are some fundamental features widely accepted in the literature. Firstly, modern construction systems often consist of pre-fabricated or modular building elements. These elements are produced in factories and can be quickly assembled on the construction site. This allows for faster completion of construction processes and time savings [39].

Furthermore, modern construction systems frequently have the potential to deliver higher-quality structures. The fabrication process takes place in a more precise and controlled environment, reducing quality losses and errors during construction [40]. This ultimately enables the construction of more durable and long-lasting buildings.

Modern construction systems can also offer advantages in terms of sustainability. The use of pre-manufactured building elements can reduce waste on the construction site [18]. Additionally, modern systems designed to increase energy efficiency and material savings can contribute to the realization of green and sustainable building projects.

In conclusion, modern construction systems offer a range of advantages such as fast construction, high quality, sustainability, and cost-effectiveness. Research conducted in the literature provides valuable insights for the widespread adoption of these innovative approaches in the construction sector. Future studies can shed more light on how these systems can be effectively utilized in various application areas and integrated into existing construction methods.

Modern construction systems have evolved to meet the evolving demands of the construction industry, which include sustainability, efficiency, and quality assurance [41]. Several key characteristics define these contemporary construction systems:

Off-site construction

Modern construction systems emphasize off-site construction methods, including prefabrication and modularization. Components are manufactured in controlled factory environments, reducing the impact of adverse weather conditions and enabling parallel construction activities. This approach accelerates project timelines [42].




Figure 2.1. Modular construction – from manufacturing to site installation [43]

Lean construction principles

Lean construction principles, borrowed from manufacturing, are central to modern construction systems. These principles aim to minimize waste, optimize resource utilization, and enhance project predictability. Lean practices contribute to cost efficiency and project quality [44].

Sustainability

Sustainable construction practices are integral to modern construction systems. These systems prioritize environmental responsibility by minimizing material waste, reducing energy consumption, and promoting recyclability. Sustainability considerations align with global efforts to address climate change and resource conservation [45].

Adaptability

Modern construction systems are designed for adaptability and flexibility. They allow for easy modifications, expansions, or repurposing of buildings, accommodating changing needs and future-proofing structures [46].

Integration of advanced technologies

These systems integrate advanced technologies such as robotics, sensors, and digital tools. These technologies enhance construction efficiency, safety, and quality [47].

In summary, modern construction systems embrace BIM technology to streamline processes, minimize waste, and deliver projects that meet the demands of sustainability and quality. These characteristics reflect the evolving landscape of construction practices and underscore the importance of integrating BIM with contemporary construction methodologies.

2.2. BIM and Modular Construction Systems: Integration Opportunities

2.2.1. Advantages and limitations of modular construction

Advantages of modular construction

Modular construction has gained significant attention and popularity in recent years due to its compelling advantages. These include:

Accelerated project schedules

Modular construction significantly reduces project timelines [48]. Modules are fabricated concurrently with on-site preparation, enabling a substantial reduction in construction schedules. This efficiency stems from the controlled factory environment in which modules are built, minimizing weather-related delays [49].

Quality control

Modular construction provides a controlled setting for module fabrication, allowing for rigorous quality control measures [50]. Comprehensive inspections and standardized processes result in higher quality and consistency, reducing defects and rework [51].

Sustainability

Modular construction aligns with sustainability goals by minimizing waste and resource consumption. Materials can be optimized for minimal waste, and unused materials can often be recycled or repurposed [52].

Cost efficiency

While there may be initial investments in manufacturing facilities, modular construction can lead to cost savings in the long run [53]. Reduced labor costs, shorter project durations, and minimized rework contribute to cost efficiency [54].

Limitations of modular construction

Despite its advantages, modular construction is not without limitations, including:

Design constraints

Modular construction imposes design constraints, as modules must adhere to standardized sizes and transportation requirements. This can limit design flexibility, particularly for unique or complex structures [55].

Transportation challenges

The transportation of large modules to the construction site may require specialized logistics and permits [56]. Transportation costs and potential challenges can affect the feasibility of modular construction for certain projects.

Site constraints

Modular construction may face limitations when dealing with constrained or inaccessible construction sites [56]. Sites with limited space for module assembly or crane access can pose challenges [48].

2.2.2. Potential alignment of BIM and modular construction systems

The integration of Building Information Modeling (BIM) with modular construction systems presents exciting opportunities and solutions to address some of the limitations and capitalize on the advantages of modular construction [57].

Design optimization

BIM's 3D modeling capabilities can be employed to design modules that seamlessly integrate into the overall building design [58]. Design constraints can be addressed through parametric modeling, allowing for customization while adhering to standardized sizes [58].

Efficient collaboration

BIM fosters real-time collaboration among project stakeholders, including architects, engineers, manufacturers, and contractors [59]. This efficient collaboration allows for instant communication of design changes, reducing the risk of miscommunication and errors [60]. BIM's data-sharing capabilities ensure that all parties work from the same information source.

Project optimization

BIM can optimize the entire project workflow, from design and fabrication to transportation and on-site assembly. This integration allows for streamlined processes and enhanced project efficiency [61].

The alignment of BIM with modular construction has the potential to maximize the benefits of both approaches, resulting in more efficient, cost-effective, and sustainable construction projects. By addressing design constraints, enhancing collaboration, and optimizing the project workflow, this integration offers a promising path forward for the construction industry.

2.3. Integration of BIM with Project Management and Quality Management

2.3.1. Relationship between BIM and project management

The integration of Building Information Modeling (BIM) with project management represents a significant advancement in the construction industry, as it offers tools and methodologies that enhance project planning, execution, and control [62].

Improved planning and scheduling

BIM provides project managers with powerful tools for creating accurate construction schedules. The 3D model allows for the visualization of construction sequences and the identification of potential clashes or conflicts in the design. This visual insight helps in optimizing project timelines and resource allocation [63].

Enhanced communication and coordination

BIM serves as a central hub for project information, facilitating communication and coordination among various stakeholders. Real-time updates and access to a common data environment minimize the risk of errors and misunderstandings [64]. The collaborative nature of BIM improves information sharing and decision-making throughout the project lifecycle.

Cost estimation and budgeting

BIM integrates cost-related information with the project model, enabling more accurate cost estimation and budgeting. Project managers can assess the financial implications of design changes in real-time [65]. This integration enhances cost control and forecasting throughout the construction process.

Resource management

BIM enables project managers to visualize and manage project resources more effectively. This includes personnel, equipment, and materials. By optimizing resource allocation, project managers can improve efficiency and reduce the likelihood of delays [66].

Risk analysis and mitigation

BIM's ability to simulate and visualize the entire construction process allows project managers to conduct comprehensive risk analysis. Identifying potential issues in advance enables proactive risk mitigation strategies [67]. This results in a more resilient project delivery process.

Quality management

BIM supports quality management by providing a detailed digital representation of the project. This includes precise geometric information, material specifications, and construction sequencing. Quality control measures can be implemented more effectively, reducing defects and rework [9].

Overall, the integration of BIM with project management enhances the efficiency and effectiveness of construction projects. By providing a comprehensive digital environment, BIM enables project managers to make informed decisions, mitigate risks, and deliver projects on time and within budget.

2.3.2. Challenges and considerations in BIM and project management integration

While the integration of BIM with project management offers significant benefits, it is not without challenges and considerations. Some of the key challenges include:

Skill and training

Successful BIM implementation requires a skilled workforce with expertise in both BIM technologies and project management methodologies. Adequate training programs are essential to equip project managers and team members with the necessary skills for effective BIM utilization [68].

Data standardization

Achieving seamless data exchange and interoperability among various BIM tools and project management software relies on standardized data formats and protocols. The industry must work towards establishing and adopting consistent data standards to ensure smooth integration [31].

Collaborative culture

The successful integration of BIM and project management necessitates a collaborative culture among project stakeholders. This includes architects, engineers, contractors, and owners. Open communication and a willingness to share information are crucial for realizing the full benefits of integration [69].

Investment costs

Implementing BIM and integrating it with project management systems involves initial investment costs, including software licenses, hardware, and training. Organizations need to assess the long-term benefits and return on investment to justify these upfront costs [70].

Project size and complexity

The suitability of BIM and project management integration may vary based on the size and complexity of the construction project [71]. Larger and more complex projects tend to benefit more from the capabilities of integrated systems, while smaller projects may find a simpler approach more practical.

Legal and contractual considerations

The integration of BIM and project management may raise legal and contractual considerations [72]. These include issues related to data ownership, intellectual property, and liability. Clear contractual agreements are essential to address these concerns and establish the responsibilities of each party.

Despite these challenges, the integration of BIM with project management offers significant advantages in terms of project efficiency, collaboration, and decision-making. As the construction industry continues to embrace digital transformation, addressing these challenges becomes crucial for successful BIM implementation and project management integration.

2.4. Utilization of Integrated BIM and Modular Construction Approach in the Design Phase

2.4.1. Modular design approach and integration with BIM

Modular design principles and their integration with Building Information Modeling (BIM) technology in the design phase of construction projects represent a transformative

approach that offers numerous advantages in terms of efficiency, collaboration, and design optimization [73].

Modular design principles

Modular design is a strategic approach that involves dividing a building into standardized, prefabricated modules or components, each with a specific function and purpose. These modules are designed to fit together seamlessly, both functionally and aesthetically, during the construction process. When integrated with BIM, these modular design principles are enhanced in several key ways:

Parametric modeling

BIM technology enables architects and designers to create parametric models of individual modules. These models are not static but dynamic, with parameters that can be adjusted to suit specific project requirements. This parametric flexibility allows for the customization of modules within standardized sizes and shapes, meeting unique design needs while maintaining the benefits of modularity [74].

Data-driven design

BIM extends beyond mere 3D visualization; it incorporates data attributes into the digital model. This data includes information about materials, structural properties, cost, and more. In the context of modular design, BIM can store and manage data related to each module, ensuring that all stakeholders have access to accurate and up-to-date information throughout the design process [75].

Design coordination

One of the central challenges in modular design is ensuring that all modules fit together seamlessly in the final construction [76]. BIM's 3D modeling capabilities enable architects and engineers to coordinate the design of each module within the larger context of the building. Clash detection tools in BIM software help identify and resolve conflicts or

interferences between modules, preventing costly design changes and construction delays [35].

Customization within standards

Modular construction often relies on standardized module sizes for efficiency in manufacturing and transportation. However, there are instances where project-specific requirements demand customization. BIM's parametric capabilities allow architects and designers to adjust module configurations while adhering to predefined dimensions. This means that modules can be tailored to meet unique design needs without compromising the benefits of modular construction, such as efficient production and assembly [77].

Benefits of integration

The integration of modular design principles with BIM technology offers several compelling benefits during the design phase of construction projects:

Efficiency

The modular approach, coupled with BIM, streamlines the design process by reusing standardized modules and components. This reduces the time required for custom design and minimizes design iterations [78].

Error reduction

BIM's clash detection tools help identify and resolve design conflicts early in the design phase. This proactive approach significantly reduces the likelihood of design errors that could lead to costly rework during construction [79].

Cost savings

Standardized modules in modular design are often more cost-effective to produce and transport. BIM's cost analysis features can help project teams make informed decisions about materials and configurations, optimizing costs during the design phase [80].

Design flexibility

The parametric modeling capabilities of BIM allow for design flexibility within standardized module sizes. This means that architects and designers can meet project-specific requirements while still benefiting from the efficiency of modular construction [81].

In summary, the integration of modular design principles with BIM technology in the design phase of construction projects represents a powerful combination of efficiency, precision, and flexibility. It enables architects and designers to create customized modular solutions within standardized parameters, streamlining the design process, reducing errors, optimizing costs, and ultimately contributing to the success of modular construction projects.

2.4.2. Enhancements in design efficiency and collaboration

The integration of Building Information Modeling (BIM) technology with modular construction practices in the design phase of construction projects brings about significant enhancements in terms of design efficiency and collaboration [82].

Real-time collaboration

Effective collaboration among design and engineering teams is crucial for the successful execution of construction projects. Historically, design processes involved multiple iterations and the exchange of drawings and documents, often leading to delays, miscommunications, and inefficiencies. However, the integration of BIM technology revolutionizes the collaborative aspects of the design phase:

Centralized data environment

BIM serves as a centralized data environment where project stakeholders, including architects, engineers, and designers, can work on the same digital model simultaneously [83]. This ensures that everyone has access to the most up-to-date project information.

Real-time updates

With BIM, changes and modifications made by one team member are instantly reflected in the digital model. This real-time updating eliminates the need for manual synchronization and reduces the risk of working from outdated information [84].

Enhanced communication

BIM fosters enhanced communication among project stakeholders by providing a common platform for discussion and collaboration. Team members can annotate the digital model, leave comments, and engage in discussions within the BIM environment. This streamlined communication streamlines decision-making processes [85].

Conflict resolution

Design conflicts or clashes, which can be a source of significant delays and rework during construction, can be addressed proactively in the digital realm of BIM. Clash detection tools within BIM software help identify and resolve conflicts between design elements. This early identification of issues reduces the likelihood of costly design changes during construction [79].

Early issue identification

Identifying and resolving design issues early in the project lifecycle is a crucial objective during the design phase. Design conflicts, inaccuracies, or oversights that go undetected until construction can have costly repercussions. The integration of BIM with modular construction enables early issue identification and resolution [33].

Virtual design reviews

BIM facilitates virtual design reviews where project stakeholders can collaboratively examine the digital model in detail. This allows for the identification of clashes or conflicts within the design. Such reviews can be conducted at various stages of the design process, ensuring that issues are discovered and addressed promptly [86].

Reduced rework

By addressing potential design issues before fabrication and construction begin, the integration of BIM and modular construction minimizes the need for costly rework and design changes [87]. This leads to significant time and cost savings, contributing to the overall efficiency of the project [88].

Improved design quality

Early issue identification and resolution enhance the overall quality of the design [33]. Designers have the opportunity to refine and optimize their work, resulting in a more robust and well-coordinated design that meets project requirements and regulatory standards [89].

Streamlined decision-making

Collaborative design reviews within the BIM environment streamlines decision-making processes. When design issues are identified, teams can quickly discuss and decide on the best course of action. This reduces delays caused by prolonged discussions and ensures that design modifications are implemented efficiently [90].

In conclusion, the integration of BIM technology with modular construction in the design phase of construction projects offers substantial enhancements in design efficiency and collaboration. Real-time collaboration, centralized data environments, and virtual design reviews streamline communication and decision-making processes. Early issue identification and resolution reduce the likelihood of costly rework during construction, ultimately contributing to the successful execution of modular construction projects.

2.4.3. Analysis and optimization of modular design through BIM

In the design phase of construction projects, the integration of Building Information Modeling (BIM) technology with modular construction practices facilitates detailed analysis and optimization of modular design, leading to more efficient and effective project outcomes.

Performance analysis

Performance analysis is a critical aspect of the design phase, ensuring that modular components meet the required standards and perform as intended. BIM technology enables rigorous performance analysis of modular design elements:

Structural integrity

Engineers can use BIM to simulate and analyze the structural integrity of modular components [91]. Finite element analysis and other tools allow for the assessment of stresses, loads, and deflections. Any structural issues can be identified and addressed before fabrication.

Energy efficiency

BIM can simulate the energy performance of modular components and the overall building [92]. This analysis helps in optimizing insulation, HVAC systems, and other energy-related design elements, contributing to enhanced sustainability and reduced operational costs.

Thermal performance

The thermal behavior of modular components can be analyzed using BIM tools [93]. Thermal modeling allows designers to assess insulation requirements, heat gain, and loss, ensuring that modules meet energy efficiency standards.

Acoustic performance

For projects with specific acoustic requirements, BIM can simulate the acoustic performance of modular components [94]. This analysis helps in optimizing soundproofing and acoustic design to meet project specifications.

Material optimization

Material optimization is a crucial aspect of both sustainable and cost-effective design. BIM technology enables project teams to optimize materials used in modular construction:

Waste reduction

By analyzing material properties and quantities within the BIM model, designers can minimize waste [95]. BIM's material takeoff features assist in precise quantity estimation, preventing overordering or shortages [96]. This waste reduction aligns with sustainability goals.

Resource efficiency

BIM facilitates the selection of resource-efficient materials [97]. Designers can explore options for materials that have a lower environmental impact while meeting performance requirements. This contributes to environmentally responsible design.

Cost estimation

BIM models can support accurate cost estimation during the design phase [98]. By linking materials, quantities, and specifications within the BIM environment, project teams can generate precise cost estimates. This helps in budget planning and cost control [99].

Cost analysis and optimization

Cost analysis and optimization play a pivotal role in design decision-making. BIM technology empowers project teams to perform detailed cost assessments and optimizations:

Cost estimation

BIM allows for accurate cost estimation by associating costs with materials, labor, and equipment [100]. This enables designers to assess the cost implications of different design choices.

Value engineering

BIM supports value engineering by facilitating the evaluation of design alternatives [101]. Designers can explore different materials, systems, and configurations to achieve cost savings without compromising quality or functionality.

Budget control

The ability to perform cost analyses within the BIM environment helps project teams in controlling budgets [102]. By making informed decisions about materials and design elements, teams can ensure that the project stays within budgetary constraints.

Sustainability

BIM's data-driven approach aids in making sustainable design choices that align with green building standards and certification requirements [103]. This includes selecting eco-friendly materials, optimizing energy performance, and minimizing waste.

The integration of BIM technology with modular construction practices in the design phase offers substantial benefits in terms of analysis and optimization. Performance analysis ensures that modular components meet required standards, while material optimization aligns with sustainability goals and cost efficiency. Detailed cost analysis and optimization enable project teams to make informed decisions that control budgets and support value engineering. By leveraging BIM's capabilities, modular construction projects can achieve a higher level of efficiency, sustainability, and cost-effectiveness, ultimately leading to successful project outcomes.

2.5. Integration of Modular Construction in Production and Assembly Phases

In the ever-evolving construction industry, the integration of modular construction methods with Building Information Modeling (BIM) technology has emerged as a transformative approach. While much attention has been given to the advantages of this integration during the design phase, its significance extends beyond initial planning and design. This comprehensive exploration delves into the utilization of BIM in the subsequent production and assembly phases of construction projects. It underscores how BIM contributes to efficient material and resource management, minimizes errors, and optimizes labor during assembly, ultimately leading to enhanced project outcomes.

The construction industry is in the midst of a paradigm shift, with modular construction gaining traction as a method that offers efficiency, sustainability, and quality. Modular construction involves the fabrication of standardized building components in a controlled factory environment, which are later transported to the construction site for assembly. Building Information Modeling (BIM), on the other hand, provides a digital representation of a building's physical and functional characteristics, facilitating collaborative design and data-driven decision-making.

While BIM has proven instrumental in the design phase of construction projects, its integration extends far beyond the drawing board. This section explores how BIM technology is harnessed in the production and assembly phases of modular construction, highlighting its pivotal role in material and resource management, error reduction, and labor optimization.

2.5.1. Utilization of BIM in production and assembly processes

Integration of BIM in construction project lifecycle

The integration of Building Information Modeling (BIM) technology in the production and assembly phases of modular construction projects is pivotal to achieving efficiency, precision, and quality throughout these stages.

Digital fabrication and precision

Digital fabrication

BIM serves as the digital blueprint for the fabrication of modular components. Manufacturers rely on the detailed digital representations of modules created in BIM to guide the production process. This digital guidance ensures that each component is precisely manufactured to meet the design specifications [77].

Precision and quality assurance

The integration of BIM in production processes enhances precision and quality assurance. By following the digital instructions derived from the BIM model, manufacturers can minimize deviations and errors in the production phase. This meticulous approach results in higher quality modular components that align closely with the original design [104].

Reduced errors

The digital nature of BIM minimizes the potential for human errors that might occur when interpreting traditional paper-based blueprints. The precision offered by BIM leads to a significant reduction in errors during the production of modular components, ultimately contributing to a higher level of quality [105].

Quality control and verification

Reference for quality control

BIM technology provides a reference point for quality control during the production phase. Manufacturers can compare the physical modular components to their digital counterparts within the BIM environment. This verification process ensures that each component is fabricated accurately, meeting the design and quality standards [106].

Error reduction

Through this quality control process, manufacturers can identify and rectify any discrepancies between the digital model and the physical component. Early identification of errors minimizes defects in the production phase, reducing the likelihood of costly rework and delays during assembly [105].

Streamlined Verification

The digital verification process facilitated by BIM streamlines quality control checks, making them more efficient and precise. Manufacturers can quickly assess the accuracy of modular components, ensuring that they are in perfect alignment with the design specifications [77].

In conclusion, BIM's integration into the manufacturing process is crucial for ensuring the quality and accuracy of modular components, vital for the success of modular construction projects. By providing a digital reference point, enabling rigorous quality control checks, and facilitating streamlined verification procedures, BIM paves the way for high-quality, efficient, and cost-effective modular construction.

Efficient assembly with digital guidance

Digital instructions

As modular components are transported to the construction site for assembly, BIM continues to play a crucial role by providing digital instructions derived from the BIM model. These digital instructions guide assembly workers in the precise and efficient assembly of modules [77].

Streamlined assembly

The digital guidance offered by BIM streamlines the assembly process, reducing the time required for on-site construction [107]. Assembly workers can follow step-by-step digital

instructions, minimizing the potential for errors and ensuring that modular components are assembled accurately.

Optimized labor

Labor optimization is a key advantage of utilizing BIM in the assembly phase. The digital guidance and precision offered by BIM enable assembly workers to perform their tasks more efficiently, ultimately reducing labor costs and ensuring that projects progress according to schedule [108].

2.5.2. Influence of BIM on material and resource management in modular production

Effective material and resource management are crucial aspects of modular construction practices. The integration of Building Information Modeling (BIM) technology in the production phase of modular construction projects significantly influences these management processes, resulting in efficiency, sustainability, and cost-effectiveness [109].

Inventory management and preventing shortages

BIM-enabled inventory management

Within BIM models, detailed data regarding material quantities and specifications are meticulously recorded [107]. Manufacturers leverage this information to manage inventory effectively. BIM serves as a digital repository of material requirements, constantly updated to reflect project needs.

Real-time visibility

The digital nature of BIM offers real-time visibility into material requirements, preventing shortages [110]. Manufacturers and project managers can access up-to-the-minute data on required materials, ensuring that the necessary components are always available when needed [111].

Preventing overordering

BIM's digital inventory management capabilities prevent overordering by providing accurate insights into material quantities [112]. Manufacturers can optimize their material procurement processes, avoiding unnecessary costs associated with excess inventory.

Reduced wastage

By preventing shortages and overordering, BIM contributes to the reduction of material wastage [113]. This aligns with sustainability goals by minimizing the environmental impact of construction projects.

Waste reduction and sustainable practices

Waste reduction is a key focus in modular construction, driven by growing concerns about sustainability. BIM technology plays a critical role in minimizing waste by optimizing material quantities and reducing errors.

Optimizing material quantities

BIM technology optimizes material quantities by providing precise digital representations. Manufacturers can cut materials accurately based on the data derived from the BIM model, minimizing waste on the factory floor. This reduction in material wastage supports sustainable construction practices [95].

Resource efficiency

BIM facilitates the selection of resource-efficient materials and processes [4,114]. Manufacturers can make informed decisions about materials that have a lower environmental impact while still meeting project requirements. This aligns with sustainability goals by promoting environmentally responsible modular production.

Cost savings through waste reduction

Reduced material wastage results in cost savings for modular construction projects [7]. BIM-driven waste reduction ensures that resources are used efficiently, contributing to the overall cost-effectiveness of the project.

Cost estimation and control

Building Information Modeling (BIM) technology significantly enhances material and resource management in modular construction, leading to improved efficiency, sustainability, and cost-effectiveness.

Accurate cost estimation

BIM models contain data linking materials, quantities, and specifications, enabling precise cost estimation [63]. This capability ensures that budgets are carefully planned and controlled during the production phase. Manufacturers and project managers can rely on BIM to generate accurate cost estimates.

Value engineering

BIM supports value engineering by allowing manufacturers to evaluate various materials and configurations [101]. This optimization process enables cost savings without compromising quality or functionality. BIM's data-driven approach aids in identifying opportunities for cost reduction.

Budget planning and control

The digital environment of BIM facilitates budget planning and control [115]. Manufacturers can monitor costs in real-time, making adjustments as needed to ensure that the project stays within budgetary constraints. This proactive approach to cost control contributes to the overall financial success of modular construction projects.

In conclusion, the influence of BIM on material and resource management in modular production is substantial. BIM technology enhances inventory management by providing real-time visibility into material requirements, preventing shortages, and reducing overordering. It also contributes to waste reduction by optimizing material quantities, supporting resource efficiency, and promoting cost-effective practices. Accurate cost estimation and budget control are facilitated through BIM, ensuring that projects stay within budgetary constraints while still meeting quality and sustainability goals. The integration of BIM technology in material and resource management processes during the production phase enhances the overall efficiency, sustainability, and cost-effectiveness of modular construction projects.

2.5.3. Impact of BIM on error reduction and labor optimization in the assembly phase

The assembly phase of modular construction is a critical juncture where errors can have significant repercussions. BIM technology is instrumental in error reduction and labor optimization during this phase:

Error prevention with digital guidance

The assembly phase in modular construction represents a critical stage where errors can lead to costly delays and rework. Building Information Modeling (BIM) technology plays a pivotal role in minimizing errors, enhancing quality, and optimizing labor efficiency during this crucial phase [116].

Precise digital instructions

BIM provides assembly workers with precise digital instructions derived from the BIM model, eliminating the need for manual interpretation of traditional paper-based blueprints [77]. These instructions offer step-by-step guidance on the placement and connection of modular components, ensuring a seamless assembly process.




Figure 2.2. Process map of BIM-enabled computerized design and fabrication of industrialized buildings with applications to modular housings. [77]

Minimized errors and reduced rework

Following BIM's digital instructions significantly reduces the likelihood of errors during assembly. The digital nature of these instructions ensures that modules are assembled accurately and according to design specifications, minimizing the need for costly rework and delays [105].

Clash detection for error mitigation

BIM's clash detection capabilities, invaluable during the design phase, continue to offer significant benefits throughout the assembly process. These tools identify and resolve conflicts between modular components in real-time, ensuring seamless construction and minimizing the likelihood of costly rework [117].

Real-time conflict resolution

As workers assemble modules, BIM's clash detection tools immediately identify and address any conflicts, preventing issues from escalating and ensuring proper component fit

[118]. This proactive approach mitigates errors and disruptions, streamlining the assembly process and minimizing delays [119].

Cost and time savings

By addressing clashes during assembly, rather than after installation, BIM saves significant time and money. It eliminates the need for disruptive and costly design changes or modifications late in the construction process [79].

Labor optimization for efficient assembly

The integration of Building Information Modeling (BIM) technology in the assembly phase of modular construction unlocks significant benefits, leading to enhanced efficiency, quality, and cost-effectiveness.

Digital guidance for labor optimization

BIM's digital guidance empowers assembly workers, enabling them to follow precise instructions and streamline the process. This optimizes labor utilization, reducing construction time and associated costs [120].

Precision and quality control

BIM promotes high-quality construction by ensuring accurate module assembly. Digital instructions minimize errors and rework, leading to a final product free of defects and issues [106].

Proactive clash detection and resolution

BIM's clash detection tools remain valuable during assembly, identifying and resolving conflicts in real-time. This proactive approach prevents costly design changes and ensures seamless module integration [119].

Schedule adherence

Optimized labor allocation and efficient assembly processes facilitated by BIM contribute to project schedule adherence. By reducing construction time, BIM minimizes the risk of delays and ensures timely project completion [121].

Holistic approach to project management

The synergy between modular construction and BIM represents a comprehensive approach to construction project management. BIM serves as a digital thread, connecting design, production, and assembly phases, ensuring consistent data flow and optimized workflows [122].

Sustainable practices and resource management

BIM promotes sustainable construction practices by facilitating material and resource optimization. This includes preventing shortages, minimizing waste, and integrating resource-efficient materials and processes [97].

In conclusion, BIM plays a vital role in error reduction and labor optimization within modular construction assembly. Its digital guidance, precise instructions, and clash detection tools minimize errors, improve quality, and optimize labor utilization. By enhancing efficiency, reducing costs, and ensuring project success, BIM and modular construction together reshape the construction landscape, paving the way for a future characterized by sustainability, efficiency, and precision.

2.6. Contribution of BIM and Modular Construction Integration to Quality Management and Monitoring

Building Information Modeling (BIM) and the integration of modular construction make significant contributions to quality management and monitoring in the construction industry. This integration plays a crucial role in ensuring that construction projects are completed in a manner that meets or exceeds standards and expectations [95]. Below are

the key contributions of BIM and modular construction integration to quality management and monitoring:

Enhanced design precision

BIM allows for highly detailed and accurate 3D modeling of modular components. Design errors and clashes can be identified and resolved in the virtual environment before physical construction begins, reducing the likelihood of quality issues on-site [123].

Consistency and standardization

Modular construction relies on the assembly of standardized building components. BIM ensures that these components are produced with precision to meet design specifications. This consistency minimizes variations and errors, ultimately enhancing overall quality [80].

Improved collaboration

BIM facilitates collaboration among various stakeholders, including architects, engineers, manufacturers, and contractors. This collaborative approach ensures that everyone is aligned with the project's quality objectives and standards [124].

Design verification

BIM software can simulate and test the behavior of modular components under various conditions, including load-bearing capacity, thermal performance, and environmental factors. This verification process helps identify potential issues and ensures that the final design meets quality criteria [125].

Quality assurance in production

BIM can provide detailed documentation and instructions for the production of modular components. Manufacturers can strictly adhere to these instructions, ensuring that the produced components meet specified quality standards [126].

Construction progress monitoring

BIM supports real-time monitoring of modular component assembly and installation. This monitoring ensures that construction progresses in alignment with the design and that any deviations are promptly identified and addressed [127].

Clash detection and resolution

BIM can identify clashes or conflicts during the assembly of modular components, such as clashes with plumbing, electrical, or HVAC systems. Early detection prevents costly rework and ensures high-quality construction [79].

Data-driven decision-making

BIM provides a wealth of data for decision-making. Project managers can analyze this data to track progress, identify quality issues, and make informed adjustments to maintain quality standards [123].

Quality inspection and testing

BIM can be integrated with quality inspection and testing protocols. Inspectors can use BIM data to verify that modular components meet required standards and specifications [8].

Documentation and maintenance

BIM maintains a digital record of the entire construction process. This record is valuable for future maintenance and renovations, ensuring the ongoing quality and performance of the structure [128].

Cost efficiency

The combination of BIM and modular construction can reduce rework, material waste, and construction delays, resulting in cost savings. These savings can be reinvested in quality management and monitoring efforts [129].

Improved communication

BIM models can be used to convey quality expectations to all project stakeholders. This shared understanding ensures that quality standards are met at every stage of the construction process [78].

2.6.1. Quality control processes in modular production

Quality control processes in modular production play a pivotal role in ensuring the reliability and performance of modular components. These processes encompass a range of activities designed to verify that each modular element meets predefined quality standards.

One key aspect of quality control in modular production is the inspection of materials and components. Materials must conform to established specifications to ensure structural integrity and durability. This includes assessing the composition, strength, and integrity of materials used in modular construction.

Furthermore, dimensional accuracy and precision are critical in modular production. BIM technology allows for the creation of highly accurate 3D models that serve as reference points for quality control [126]. Inspecting modular components against these 3D models helps identify any deviations or discrepancies.

Additionally, the assembly of modular components requires meticulous attention to detail. Quality control processes involve examining the connections, joints, and interfaces between modular units [130]. Ensuring that these connections are secure and meet design specifications is essential for the overall structural integrity of the construction.

Non-destructive testing methods, such as ultrasound or X-ray inspections, can be applied to identify potential defects or weaknesses within modular components [106,126]. These methods enable early detection of issues that may compromise the quality of the final assembly.

Continuous monitoring throughout the modular production process is another key element of quality control. Real-time data and sensor-based technologies can be employed to track and analyze the quality of components as they are being manufactured. This proactive approach enables rapid adjustments and corrections, minimizing the potential for defects.

2.6.2. BIM-based monitoring and quality assurance

BIM-based monitoring and quality assurance serve as essential tools for maintaining high construction standards in modular projects [131]. BIM technology provides a digital environment where various quality-related activities can be carried out.

One fundamental aspect of BIM-based quality assurance is clash detection. BIM models enable the identification of clashes or conflicts between different components, systems, or disciplines within the modular construction [132]. By detecting these clashes early in the design phase, potential quality issues are mitigated.

Furthermore, BIM allows for the simulation of the assembly process, providing insights into constructability and feasibility [133]. This simulation-based approach aids in verifying that modular components can be assembled as intended, minimizing on-site challenges and ensuring quality.

BIM also facilitates real-time monitoring of construction progress. By comparing the as-built conditions to the BIM model, project managers can ensure that construction aligns with the original design, and any deviations are promptly addressed [134]. This ongoing monitoring enhances quality assurance.

2.6.3. Enhancements in quality and performance within modular construction systems

The integration of BIM and modular construction systems yields significant enhancements in quality and performance. The ability to create precise 3D models of modular components ensures consistency and standardization.

Modular construction systems benefit from the reduction in errors and rework due to early clash detection and constructability analysis [135]. This results in a more efficient construction process and a higher level of quality.

Moreover, data-driven decision-making, enabled by BIM, empowers project managers to make informed adjustments to maintain quality standards. This proactive approach fosters continuous improvement and ensures that quality remains a top priority [136].

In summary, quality control processes, BIM-based monitoring, and performance enhancements are integral to achieving and maintaining high standards in modular construction. These approaches work in tandem to minimize errors, ensure structural integrity, and provide a framework for delivering quality modular buildings and infrastructure.

2.7. Impact of Project Management and BIM-MPS Integration on Project Success

The integration of project management and Building Information Modeling with Modular Project Scheduling (BIM-MPS) has a profound impact on project success. This integration brings numerous benefits, influences project planning and monitoring, and enhances risk management and decision-making processes [137].

2.7.1. Benefits of project management and BIM integration

The integration of project management with BIM technology significantly enhances project success. One of the key benefits is improved communication and collaboration among project stakeholders [138]. BIM serves as a common platform for sharing project

information, enabling better coordination and reducing the likelihood of misunderstandings or errors.

Furthermore, BIM facilitates a more efficient project planning process. Project managers can create detailed 3D models that serve as the basis for project schedules and resource allocation [139]. This results in a more accurate project plan and timeline, reducing the risk of delays.

Project management and BIM integration also enhance project monitoring. Real-time updates from the construction site can be compared to the BIM model, allowing project managers to track progress and identify deviations. This proactive monitoring improves the ability to address issues promptly, ensuring that the project stays on track.

Additionally, the integration of project management and BIM supports better resource management. Project managers can allocate resources more effectively by utilizing the information provided by the BIM model. This optimizes resource utilization and reduces costs, contributing to project success.

2.7.2. Influence of BIM-MPS integration on project planning and monitoring

The integration of BIM-MPS has a significant influence on project planning and monitoring [140]. BIM-MPS combines the benefits of BIM with modular project scheduling techniques to further enhance project success.

In project planning, BIM-MPS allows for the precise modeling and sequencing of modular components. Project managers can create detailed schedules that include the assembly and installation of modular units [140,7]. This level of detail in planning minimizes uncertainty and increases the likelihood of successful project execution.

Project monitoring is greatly improved through BIM-MPS integration. Modular project scheduling enables project managers to track the progress of modular component manufacturing and delivery [140,7]. This detailed monitoring ensures that modular components are available as needed, reducing delays and disruptions to the project timeline.

Moreover, BIM-MPS enables real-time visibility into the entire project. Project managers can compare the progress of modular construction with the BIM model, ensuring that the as-built conditions align with the design [7]. Any discrepancies are promptly addressed, maintaining project quality and success.

2.7.3. Integration of risk management and decision-making processes through BIM-MPS

The integration of BIM-MPS also improves risk management and decision-making processes. By combining BIM's data-driven insights with modular project scheduling, project managers can better mitigate risks and make informed decisions. Risk management benefits from BIM-MPS integration through improved risk identification and assessment. Project managers can use the BIM model to identify potential clashes or constructability issues in the modular components [141]. Early detection of these risks allows for proactive risk mitigation.

Additionally, decision-making processes are enhanced through the integration of BIM-MPS. Project managers have access to real-time data and insights from the modular construction process [174]. This data-driven decision-making approach supports adjustments and adaptations to maintain project success, even in the face of unexpected challenges.

In summary, the integration of project management with BIM and BIM-MPS has a substantial impact on project success. It brings benefits such as improved communication, efficient planning, and enhanced project monitoring. The influence on project planning and monitoring is profound, with real-time visibility and detailed scheduling. Moreover, risk management and decision-making processes are bolstered, contributing to overall project success.

3. RESEARCH METHOD AND MATERIAL

This research aims to ascertain whether the utilization of Building Information Modeling (BIM) in the modular construction industry contributes to an enhancement in quality. Academic papers pertaining to BIM and modular construction were meticulously collected from an extensive online dataset, aligning with the objectives outlined in this comprehensive review study. Scopus database was the preferred choice for researching the positive impact of BIM on quality improvement in modular construction, given its multifaceted advantages.

The research process involved a conscientious delineation of the study's scope, ensuring a thorough exploration of pertinent articles within the specified domains. This clear definition facilitated the development of an effective and targeted search strategy, encompassing the breadth and depth of literature associated with BIM and modular construction.

The research methodology employed in this study embraced a systematic and meticulous approach, leveraging both bibliometric analysis and a systematic literature review (SLR). This dual-pronged methodology enabled a rigorous examination of the scholarly landscape surrounding BIM and modular construction. The application of a science mapping approach, an integral component of the methodology, facilitated the visualization of relationships and interconnections within the academic literature. The Scopus online database, with its extensive coverage and wealth of scholarly resources, played a pivotal role in providing the primary data necessary for the thorough execution of this research. Scopus encompasses a broad scope, including various disciplines such as engineering, architecture, and construction, providing access to a diverse range of academic articles and studies related to modular construction and BIM. The database is recognized for its inclusion of content from highly impactful and respected journals, ensuring a reliable foundation for research based on quality sources. Notably, Scopus stands out for its comprehensive indexing of conference proceedings, making it valuable for researchers focusing on specific technical and engineering subjects. Its international perspective, incorporating scientific publications from around the world, facilitates an exploration of international studies on modular construction and BIM, providing insights into different

applications and experiences across various geographical regions. The citation indexing feature in Scopus further aids researchers in assessing academic activity in the field by indicating the number of times articles have been cited. Lastly, the database's regular updates ensure access to the latest research and developments in modular construction and BIM usage. In conclusion, Scopus is frequently favored by researchers for its comprehensive and reliable features, making it a pragmatic selection for substantiating hypotheses concerning the potential positive impact of BIM on quality improvement in modular construction.

Furthermore, this study aimed to identify gaps in the existing literature regarding the application of BIM and modular construction. Analyzing the selected papers through the PDCA lens helped identify areas where further research is needed to fully understand and optimize the implementation of these technologies. The selected papers were further analyzed using the PDCA (Plan-Do-Check-Act) cycle to evaluate the implementation and effectiveness of BIM and modular construction practices. The main purpose of using the PDCA (Plan-Do-Check-Act) cycle in this study was to understand the potential of using Building Information Modeling (BIM) to improve quality in the modular construction industry. The PDCA analysis conducted on 19 articles revealed how we can contribute to quality improvement by providing important information on how to implement BIM and evaluate its effectiveness. This process provided a structured framework for evaluating and optimizing learnings from the design of the study. This information will be invaluable in guiding future research efforts and contributing to the advancement of knowledge in this field.

In essence, the methodology adopted for this review study was thoughtfully designed to ensure a comprehensive, in-depth, and methodologically sound analysis of academic papers related to BIM and modular construction. By employing a combination of bibliometric analysis, SLR, science mapping, and PDCA analysis, the study provided valuable insights into the current state of research in this field while simultaneously identifying areas for further exploration and investigation.




Figure 3.1. Flow diagram of the search methodology

3.1. Bibliometric Analysis

Data for necessary academic documents are retrieved via bibliometric searches. Scopus is one of the most extensive databases on the internet. In order to review the most recent research on BIM and modular construction projects in the construction industry, the Scopus database was used in this paper. The most recent publications are also included in the Scopus database. The database used for this review thesis was the Scopus database. The following keywords were used to retrieve articles about project BIM and modular construction in order to conduct a thorough literature review: ("modular construction") AND ("quality") AND ("Building Information Modeling" OR "BIM"), and the search was limited to the following terms: titles, abstracts, and keywords. The research subjects were limited to Engineering, Computer Science, Business Management and Accounting, Decision Sciences, Social Sciences, Arts and Humanities, and Multidisciplinary, which are related to the construction domain. Only English journal and conference proceedings papers were selected for this review.

Research query was carried out on 9 December 2023 with the following final string: (TITLEABS-KEY ("Building Information Modeling" OR "BIM" OR) AND TITLE-ABS-KEY ("modular construction") AND TITLE-ABS-KEY ("quality")) AND INCLUDED "ENGINEERING" OR "COMPUTER SCIENCE" OR "BUSINESS MANAGEMENT AND ACCOUNTING" OR "DECISION SCIENCE" OR "SOCIAL SCIENCE" OR "ARTS AND HUMANITIES" OR "MULTIDISCIPLINARY". EXCLUDED "MATHEMATICS" OR "ENERGY" OR "MATERIALS SCIENCE" OR "EARTH AND PLANETARY SCIENCES" OR "CHEMISTRY" OR "PHYSICS AND ASTRONOMY" OR "AGRICULTURAL AND BIOLOGICAL SCIENCES" OR "CHEMICAL ENGINEERING" OR "BIOCHEMISTRY" OR "GENETICS AND MOLECULAR BIOLOGY" OR "MEDICINE"). After this scan, the dataset contained 343 documents. The other assessment process involved reviewing the titles and abstracts of documents to identify only those that were relevant to the field of building information modelling and modular construction. The number of documents related to both BIM and modular construction is 179. After an extensive manual filtering process, including quality, the final dataset contained 46 documents (Figure 3.1).




Figure 3.2. Graph of 46 articles written between 2006-2023 for BIM, MCS and quality by year (Scopus)

The evaluation of 46 articles encompassing Building Information Modeling (BIM), modular construction, and quality presents a quantitative perspective, with a notable focus on the years 2022 and 2023 (Figure 3.2). These articles have garnered significant attention, particularly in leading construction nations such as the USA, China, and South Korea. The surge in publications from these countries underscores the widespread interest and adoption of innovative technologies in the construction sector (Figure 3.3).




Figure 3.3. Chart of 46 articles written between 2006-2023 for BIM, MCS and quality by country (Scopus)

The findings emphasize how the integration of BIM and modular construction contributes to achieving and maintaining high-quality standards while enhancing overall efficiency in construction processes. The increasing number of publications in these regions reflects the rapid ascent of these technologies. Furthermore, the subjects addressed in these articles provide valuable quantitative data for stakeholders in the construction industry to make informed decisions. These studies underscore the concrete impact of the convergence of BIM, modular construction, and quality trends in the industry, offering guidance for the planning and execution of future construction projects.

Another examination conducted through VOSviewer involved a detailed analysis of the keywords from the 46 articles. This analysis utilizes an interactive visualization tool to unveil common themes and connections within the literature. The transitions between keywords in the articles highlight robust relationships between topics, while prominent terms help identify overarching research trends. The analysis further illustrates how key terms related to BIM, modular construction, and quality stand out among the articles and how these terms interrelate. Thus, the VOSviewer analysis provides an in-depth understanding of the content of the 46 articles, contributing to our comprehension of the evolution and relationships of keywords in the literature on these topics (Figure 3.4).




Figure 3.4. Analysis of 46 articles written between 2006-2023 for BIM, MCS and quality according to keywords made in VOSviewer

3.2. Systematic Review Analysis

Systematic review analysis is described as "a quantitative study of research on the development of science" by the authors. It is a method for mapping a particular body of knowledge using trends taken from academic databases by evaluating the influence of research and looking at citation relationships. Even though a manual review of the literature can offer a thorough overview of a certain field of study, it is still prone to bias and interpretive limitations. In order to visualize and map the knowledge area, BIM and modular construction projects within the construction domain are analyzed using the systematic review technique in this study. Using information from systematic reviews, the bibliometric analysis method creates a network model and identifies research subjects. By creating network models that represent the intellectual viewpoint on a specific body of knowledge, systematic review analysis helps researchers answer their research questions and accomplish their goals. Researchers will be able to perceive overall research patterns and identify research trends with the help of visualizing the field of building information modeling as a network. The publications' contents are briefly summarized in the abstract and keywords. As a result, clusters corresponding to the most important elements of the research area are created using keywords as the unit of analysis. This review paper conducted a thorough literature search on building information modeling by utilizing the title, abstract, and keyword codes in a bibliometric search. This approach has been suggested before for carrying out a thorough analysis of the literature.

The systematic analysis of relevant literature and articles has led to the formulation of six hypotheses supporting the assertion that the combined use of Building Information Modeling (BIM) and modular construction contributes to an enhancement in quality. These hypotheses serve as theoretical foundations for further exploration and empirical validation of the impact of BIM and modular construction on the quality of construction projects.

The formulation of hypotheses regarding the positive impact of Building Information Modeling (BIM) on the quality of modular construction is underpinned by the multifaceted capabilities that BIM introduces to the construction landscape. As a transformative technology, BIM is recognized for its potential to address challenges inherent in modular construction and contribute significantly to the improvement of project quality. The following hypotheses delineate specific aspects through which BIM is anticipated to exert

a positive influence on modular construction quality. These hypotheses not only serve as guiding principles for empirical investigation but also underscore the intricate ways in which BIM, with its collaborative, precision-oriented, and communication-enhancing features, can potentially elevate the standards of quality within the modular construction paradigm. Through systematic examination and validation, these hypotheses aim to contribute substantively to our understanding of the synergies between BIM implementation and enhanced quality outcomes in the dynamic realm of modular construction.

3.3. Enhancing Modular Construction Quality through BIM: Hypotheses

A Fishbone diagram has been constructed based on the literature review, illustrating that the combined utilization of Building Information Modeling (BIM) and modular construction enhances quality. This diagram has been designed to systematically visualize the positive impacts of the concurrent use of BIM and modular construction on quality. By identifying key cause-and-effect relationships, the diagram categorizes specific factors under overarching titles to elucidate how the combined use of BIM and modular construction contributes to the improvement of quality.

The Fishbone diagram classifies factors such as improvements in design processes, increased efficiency in construction processes, and strengthened communication and collaboration under main categories. The interconnections between these elements within the diagram elucidate how the integration of BIM and modular construction collectively enhances quality (Figure 3.5).

This Fishbone diagram serves as a visual representation of a comprehensive analysis of existing literature, systematically presenting evidence that the combined use of BIM and modular construction plays a crucial role in enhancing quality. This visual analysis, derived from a deep exploration of available information in the literature, underscores the potential of BIM and modular construction to improve quality. It provides a significant foundation for guiding future research endeavors and projects by highlighting the positive implications of integrating BIM and modular construction for quality enhancement.




Figure 3.5. Ishikawa diagram showing that the use of modular construction with BIM increases the quality (Prepared by Author)

3.3.1. Hypothesis 1: Improved efficiency and reduced delays

Hypothesis: The integration of Building Information Modeling (BIM) and modular construction methods, such as modular construction, enhances project efficiency by streamlining processes and minimizing delays through better coordination and planning.

BIM technology can improve efficiency and reduce losses due to project delays by using a three-dimensional representation to identify and address loopholes in a timely manner. (1)

BIM's powerful information integration and sharing function helps solve problems faced by the construction industry, such as low production efficiency, by subverting traditional production paradigms. (2)

The use of BIM technology in construction can improve quality, expenditure control, and logistics management. (3)

BIM technology has been widely used in the construction industry, accelerating its development and ensuring the reliability of structural design. (4)

BIM technology can be used throughout the life cycle of a construction project, providing benefits in various aspects of construction engineering. (5)

BIM can help ensure the efficiency and quality of engineering construction through a scientific management system. (6)

BIM technology can be used for visualization, coordination, simulation, optimization, and drawing, providing technical means for optimizing each stage of a project and improving work efficiency. (7)

Table 3.1. Article table based on the ‘Improved Efficiency and Reduced Delays’ hypothesis

No	Author(s)	Year	Title	Journal
1	Zhang, L., & Liu, H.	2021	<i>Research on Application Strategy of BIM Technology in Construction Project Management</i>	E3S Web of Conferences
2	Wang, M., Qian, Y., Yuan, R., & Wang, Q.	2019	<i>Visual Analysis on Evolution, Hotspots and Frontier of International BIM Research - Literature Metrology Based on Web of Science Database</i>	Tiedao Xuebao/Journal of the China Railway Society
3	Volkov, A., Chelyshkov, P., & Lysenko, D.	2016	<i>Information Management in the Application of BIM in Construction: The Roles and Functions of the Participants of the Construction Process</i>	Procedia Engineering
4	Cao, Y., & Li, Y.	2021	<i>The Study on Design Method of Assembly Structure Based on Computer BIM Technology</i>	Journal of Physics: Conference Serie

Table 3.1. (continues)Article table based on the ‘Improved Efficiency and Reduced Delays’ hypothesis

5	Qiu, S., Xu, H., Jin, J., Zhang, H., & Sun, K.	2019	<i>Application of BIM Technology in Construction Engineering</i>	IOP Conference Series: Earth and Environmental Science
6	He, L., Xie, Y., & Li, Y.	2022	<i>Application and Research of Data Mining Technology BIM and Internet of Things in Engineering Construction</i>	Lecture Notes on Data Engineering and Communications Technologies
7	Lv, M., Zhou, L., Wang, Y., Yang, K., & Yang, C.	2022	<i>Summary of BIM Technology Application in a Dormitory Building Project</i>	Advances in Transdisciplinary Engineering

3.3.2. Hypothesis 2: Expenditure control and logistics management

Hypothesis: The utilization of BIM, coupled with modular construction practices, enables effective control of project expenditures and logistics. This is achieved through detailed cost modeling and optimized material and resource management.

BIM technology improves the quality of construction and logistics management by providing effective tools for expenditure control and information integration. (1)

BIM subverts the traditional production paradigm of the construction industry, solving problems such as information loss and low production efficiency. (2)

The application of BIM in construction engineering helps construct a scientific management system, ensuring the efficiency and quality of engineering construction. (3)

BIM-based management of construction processes is becoming a major requirement in the construction industry, promoting better development. (4)

Table 3.2. Article table based on the ‘Expenditure Control and Logistics Management’ hypothesis

No	Author(s)	Year	Title	Journal
1	Volkov, A., Chelyshkov, P., & Lysenko, D.	2016	<i>Information Management in the Application of BIM in Construction. The Roles and Functions of the Participants of the Construction Process</i>	Procedia Engineering
2	Wang, M., Qian, Y., Yuan, R., & Wang, Q.	2019	<i>Visual Analysis on Evolution, Hotspots and Frontier of International BIM Research - Literature Metrology Based on Web of Science Database</i>	Tiedao Xuebao/Journal of the China Railway Society, 41(6), 9-15
3	He, L., Xie, Y., & Li, Y.	2022	<i>Application and Research of Data Mining Technology BIM and Internet of Things in Engineering Construction</i>	Lecture Notes on Data Engineering and Communications Technologies
4	Isikdag, U.	2015	<i>The future of building information modelling: BIM 2.0. In SpringerBriefs in Computer Science (Vol. 0, pp. 13-24)</i>	Springer

3.3.3. Hypothesis 3: Enhanced communication and information management

Hypothesis: BIM facilitates improved communication and information management throughout the construction process. When combined with modular construction, it allows for real-time data sharing, reducing errors and enhancing overall project communication.

BIM is a powerful tool that integrates and shares information, helping to solve problems faced by the traditional construction industry, such as information loss and low production efficiency. (1)

BIM improves communication and information flow between stakeholders involved in all stages of construction, reducing manual re-entering of information and increasing efficiency. (2)

The use of BIM in the construction process improves the design process and helps mitigate challenges in the interface between design and construction, such as deficiencies and errors in the design. (3)

Table 3.3. Article table based on the ‘Enhanced Communication and Information Management’ hypothesis

No	Author(s)	Year	Title	Journal
1	Wang, M., Qian, Y., Yuan, R., & Wang, Q.	2019	<i>Visual Analysis on Evolution, Hotspots and Frontier of International BIM Research - Literature Metrology Based on Web of Science Database</i>	Tiedao Xuebao/Journal of the China Railway Society, 41(6), 9-15
2	Borrmann, A., König, M., Koch, C., & Beetz, J.	2018	<i>Building information modeling: Why? What? How? In Building Information Modeling: Technology Foundations and Industry Practice (pp. 1-24)</i>	Springer International Publishing
3	Svalestuen, F., Knotten, V., Lædre, O., Drevland, F., & Lohne, J.	2017	<i>USING BUILDING INFORMATION MODEL (BIM) DEVICES TO IMPROVE INFORMATION FLOW AND COLLABORATION ON CONSTRUCTION SITES</i>	Journal of Information Technology in Construction, 22, 204-219

3.3.4. Hypothesis 4: Holistic approach throughout the construction life cycle

Hypothesis: The combined use of BIM and modular construction supports a holistic approach throughout the construction life cycle. This includes design, fabrication, transportation, and assembly, resulting in a more integrated and efficient construction process.

BIM technology improves the quality of construction, expenditure control, and logistics management. (1)

BIM has great potential in construction engineering and is a rapidly evolving field. (2)

BIM subverts the traditional production paradigm of the construction industry and helps solve problems such as information loss and low production efficiency. (3)

BIM technology can participate in the entire process of building construction projects, ensuring smooth development, efficiency, and reduced losses. (4)

BIM technology can be used throughout the life cycle of construction, providing benefits in all aspects of construction engineering. (5)

BIM helps ensure the efficiency and quality of engineering construction and promotes the better development of the construction industry. (6)

Table 3.4. Article table based on the ‘Holistic Approach throughout the Construction Life Cycle’ hypothesis

No	Author(s)	Year	Title	Journal
1	Volkov, A., Chelyshkov, P., & Lysenko, D.	2016	<i>Information Management in the Application of BIM in Construction. The Roles and Functions of the Participants of the Construction Process</i>	Procedia Engineering
2	Heng, L. I., & Hong-Yu, L. I.	2020	<i>Applications of BIM in Construction Engineering in China: A Review</i>	E3S Web of Conferences
3	Wang, M., Qian, Y., Yuan, R., & Wang, Q.	2019	<i>Visual Analysis on Evolution, Hotspots and Frontier of International BIM Research - Literature Metrology Based on Web of Science Database</i>	Tiedao Xuebao/Journal of the China Railway Society, 41(6), 9-15
4	Zhang, L., & Liu, H.	2021	<i>Research on Application Strategy of BIM Technology in Construction Project Management</i>	E3S Web of Conferences
5	Qiu, S., Xu, H., Jin, J., Zhang, H., & Sun, K.	2019	<i>Application of BIM Technology in Construction Engineering</i>	IOP Conference Series: Earth and Environmental Science
6	He, L., Xie, Y., & Li, Y.	2022	<i>Application and Research of Data Mining Technology BIM and Internet of Things in Engineering Construction</i>	Lecture Notes on Data Engineering and Communications Technologies

3.3.5. Hypothesis 5: Enhanced collaboration and stakeholder engagement

Hypothesis: BIM and modular construction foster collaboration and stakeholder engagement by providing a shared platform for all project participants. This promotes effective communication and collaboration among architects, engineers, contractors, and other stakeholders.

BIM-based Construction Networks (BbCNs) focus on collaboration within teams to undertake BIM-related tasks on projects. However, research has shown that collaboration on BIM-enabled projects has predominantly focused on technology, while project-related and managerial antecedents have remained under-researched. (1)

Collaboration aspects in BIM implementation have been found to produce the highest positive impact, with process aspects being more important than software technology. However, there is a lack of industry expertise and training, which provides an opportunity for education providers. (2)

A modified model for collaboration in BbCNs has been proposed, taking into account influential factors and their sub-factors, including unfavorable BIM contractual arrangements as a root cause of the unwillingness of team members to engage in collaborative efforts. (3)

Table 3.5. Article table based on the ‘Enhanced collaboration and stakeholder engagement’ hypothesis

No	Author(s)	Year	Title	Journal Name
1	Oraee, M. et al.	2017	<i>Collaboration in BIM-based Construction Networks: A Bibliometric-Qualitative Literature Review</i>	International Journal of Project Management
2	Eadie, R. et al.	2013	<i>BIM Implementation throughout the UK Construction Project Lifecycle: An Analysis</i>	Automation in Construction
3	Oraee, M. et al.	2022	<i>Collaboration in BIM-based Construction Networks: A Qualitative Model of Influential Factors</i>	Engineering, Construction and Architectural Management

3.3.6. Hypothesis 6: Improved quality through cost management

Hypothesis: The integration of BIM with modular construction contributes to effective cost management by offering accurate cost estimations, monitoring project expenditures, and identifying potential cost-saving opportunities throughout the construction project.

The combined use of BIM (Building Information Modeling) and modular construction in construction projects has been shown to increase quality through cost management.

Several studies have highlighted the benefits of using BIM technology in construction, including improved expenditure control, logistics management, and engineering cost management. (1,2,3,4,5,6,7)

BIM technology allows for better modeling and measurement, construction schedule planning, site layout, and project cost analysis. (2)

It also enables dynamic monitoring of construction progress and cost, leading to more effective cost management. (3)

By using BIM, project costs can be managed scientifically and precisely, resulting in reduced costs and improved project implementation. (4,7)

Table 3.6. Article table based on the ‘Improved quality through cost management’ hypothesis

No	Author(s)	Year	Title	Journal Name
1	Volkov, A., Chelyshkov, P., & Lysenko, D.	2016	<i>Information Management in the Application of BIM in Construction. the Roles and Functions of the Participants of the Construction Process</i>	Procedia Engineering
2	Li, R., Zhao, H., Wang, X., & Wang, Y.	2023	<i>Research on Construction Organization Design and Engineering Cost Application Based on BIM Technology</i>	Journal of Physics: Conference Series
3	Ding, C.	2023	<i>Construction Management Mode of Building Engineering Based on BIM Technology</i>	Lecture Notes on Data Engineering and Communications Technologies
4	Wang, N.	2020	<i>Research on fine management of engineering cost based on BIM technology</i>	Journal of Physics: Conference Series
5	Wen, Z.	2019	<i>Application Research of BIM Technology in Engineering Cost Management</i>	IOP Conference Series: Earth and Environmental Science
6	He, L., Xie, Y., & Li, Y.	2022	<i>Application and Research of Data Mining Technology Bim and Internet of Things in Engineering Construction</i>	Lecture Notes on Data Engineering and Communications Technologies
7	Mo, L.	2018	<i>Research on Application of BIM Technology in Construction Project Cost Management</i>	Proceedings - 2018 3rd International Conference on Smart City and Systems Engineering, ICSCSE 2018

The analysis, based on the examination of 19 articles, has culminated in the creation of a graphical representation depicting the distribution of publications across various hypotheses. The graph reveals the prevalence of each hypothesis within the corpus of literature, shedding light on the frequency with which these hypotheses have been explored. Notably, seven articles specifically address the "Improved Efficiency and Reduced Delays" hypothesis, delving into how the concurrent use of Building Information Modeling (BIM) and modular construction enhances project efficiency and minimizes

delays. Four articles focus on the "Expenditure Control and Logistics Management" hypothesis, investigating how the integration of BIM and modular construction impacts financial control and logistical aspects of construction projects.

Furthermore, three articles contribute to the exploration of the "Enhanced Communication and Information Management" hypothesis, emphasizing the role of BIM and modular construction in bolstering communication and information flow within construction processes. The hypothesis related to a "Holistic Approach throughout the Construction Life Cycle" is addressed by six articles, offering insights into how BIM and modular construction contribute holistically across different phases of a construction project.

Additionally, three articles delve into the "Enhanced collaboration and stakeholder engagement" hypothesis, examining the collaborative aspects and stakeholder engagement facilitated by the concurrent use of BIM and modular construction. Finally, seven articles center around the "Improved quality through cost management" hypothesis, providing an in-depth exploration of how BIM and modular construction influence cost-related aspects in the construction domain. (Figure 3.6).




Figure 3.6. Numerical graph according to hypotheses (Prepared by Author)

A graphical representation depicting the distribution of publications related to Building Information Modeling (BIM) and modular construction across different years has been

generated based on the examination of 19 articles. The graph spans from 2013 onwards, providing a comprehensive view of the yearly publication trends in these specific research areas. Analyzing the number of articles published each year reveals insights into the evolving emphasis on BIM and modular construction in the literature.

This graphical representation allows us to observe how the number of publications in the field has fluctuated or intensified over the years, offering a nuanced perspective on the temporal evolution of research interests. Since 2013, the graph illuminates the changing landscape of literature dedicated to BIM and modular construction, showcasing periods of increased or decreased scholarly attention.

By visually capturing the year-wise distribution of articles, this graph serves as a valuable tool for understanding the temporal dynamics of research focus within the realms of BIM and modular construction. It aids in identifying trends and patterns, facilitating the development of strategic directions for future research initiatives. This visual analysis contributes to a clearer understanding of the temporal changes in literature dedicated to BIM and modular construction topics (Figure 3.7).




Figure 3.7. Year distribution graph according to hypotheses (Prepared by Author)

A graph depicting the countries where the examined 19 articles were published has been generated in accordance with the extracted hypotheses. This analysis visually represents the geographic distribution of studies in the literature based on the formulated hypotheses. Notably, China stands out as the most prolific contributor in this field, hosting 21 articles and solidifying its leadership position in research endeavors related to the formulated hypotheses. The United States follows with four articles, sustaining its significant scholarly contributions in the field. Other countries have made varying degrees of contributions with fewer articles. This graph, aligned with the formulated hypotheses, provides a clear representation of the global academic interest and contribution in the field of Building Information Modeling (BIM) and modular construction, helping us understand the worldwide distribution of research efforts in these areas (Figure 3.8).




Figure 3.8. Country distribution graph according to hypotheses (Prepared by Author)

3.4. Continuous Improvement in Construction Quality: Validating the Impact of BIM through the PDCA Cycle

The Plan-Do-Check-Act (PDCA) cycle is a systematic and iterative approach that has proven to be instrumental in enhancing quality management processes. In the Plan phase, organizations establish objectives and identify processes required to deliver high-quality outcomes. This initial planning sets the foundation for the subsequent phases. The Do

phase involves the execution of the plan, where strategies are implemented, and actions are taken to meet the specified quality goals. The crucial Check phase follows, during which performance and results are systematically monitored and compared against the predetermined objectives. This step allows for the identification of any variances or deviations from the planned processes. Finally, in the Act phase, adjustments and improvements are made based on the findings from the Check phase, closing the loop and ensuring a continuous cycle of improvement. The PDCA cycle, with its emphasis on planning, execution, evaluation, and refinement, provides a structured and dynamic framework for organizations to continuously enhance their quality management methods. This cyclical process fosters adaptability, responsiveness, and a commitment to ongoing improvement in the pursuit of optimal quality outcomes.

The use of BIM and modular construction together is an effective way to improve quality in the construction industry. This approach helps to improve quality at all stages of the PDCA cycle. The PDCA cycle is an important method for controlling construction quality. BIM is comprehensively applied to this cycle, ensuring better construction project quality.




Figure 3.9. PDCA Cycle (Prepared by Author)

In the planning stage, the use of BIM and modular construction helps to better understand and design the project. BIM creates a digital model of all the project's components, making it possible to identify design errors and inconsistencies early on. Modular construction, on

the other hand, allows the project to be built by assembling pre-fabricated modules. This helps to ensure that the design is more accurate and consistent.

In the doing stage, the use of BIM and modular construction helps to build the project more efficiently. BIM allows the construction process to be managed digitally. This helps to improve labor and material efficiency. Modular construction, on the other hand, requires less labor and time on the construction site. This helps to reduce construction costs and time.

In the checking stage, the use of BIM and modular construction helps to better track the quality of the project. BIM allows progress and performance to be tracked. This helps to determine whether the project meets requirements. Modular construction, on the other hand, allows the project to be built from pre-tested and approved modules. This helps to improve the quality and reliability of the project.

In the acting stage, the use of BIM and modular construction helps to take the necessary measures to improve the quality of the project. BIM helps to identify opportunities for improvement by analyzing the project's performance. Modular construction, on the other hand, helps to develop new approaches to improving the quality of the project.

The 19 selected articles were examined in detail within the framework of the Plan-Do-Check-Learn (PDCA) cycle. In the first phase, "Plan", the general aims, research questions and methods of the articles were meticulously evaluated. This step enabled the creation of a clear plan for the objectives of the research. Then, in the "Do" phase, the data collection, analysis and conclusion drawing processes of the articles were discussed in detail. This step allowed researchers to critique the methods used in terms of reliability and validity.

In the "Check" phase, the results and implications of the articles were comprehensively evaluated. Statistical analysis identified the strengths and weaknesses of the findings. Additionally, a rigorous checking process was applied to detect methodological errors and conflicting results. Finally, in the "Act" phase, the applicability of the PDCA cycle on these articles was discussed. Learnings from the studies were presented systematically, along with suggestions for similar future studies.

Within the scope of the study, an evaluation based on the Plan-Do-Check-Learn (PDCA) cycle was carried out through a table created with data obtained from 19 articles. As a result of the review in the table, deficiencies were detected in some articles at this stage. This analysis aims to create a more solid foundation by focusing on the shortcomings while highlighting the strengths of the articles as a result of a systematic evaluation with the PDCA cycle. Missing stages of the articles are left blank in the table.

Table 3.7. Table of 19 articles by PDCA assessment

No	Author(s)-Title	Plan	Do	Check	Act
1	Zhang, L., & Liu, H. <i>Research on Application Strategy of BIM Technology in Construction Project Management</i>	The purpose of the paper is to research the application strategy of BIM technology in the field of construction project management.	The article contains recommendations necessary to support the application strategy of BIM technology in the field of construction project management.		The article involves measuring the efficiency, effectiveness and quality of application of BIM technology in the field of construction project management
2	Wang, M., Qian, Y., Yuan, R., & Wang, Q. <i>Visual Analysis on Evolution, Hotspots and Frontier of International BIM Research- Literature Metrology Based on Web of Science Database</i>	The purpose of the paper is to visually analyze the evolution, hotspots, and frontiers of BIM research.		The article involves evaluating research using indicators such as publication volume, number of citations, and impact factor to identify leading areas of international BIM research.	

Table 3.7. (continues)Table of 19 articles by PDCA assessment

3	Volkov, A., Chelyshkov, P., & Lysenko, D. <i>Information Management in the Application of BIM in Construction: The Roles and Functions of the Participants of the Construction Process</i>	The purpose of the paper is to examine the role and functions of information management in the application of BIM technology in construction engineering.			The article covers the potential benefits that information management can provide in implementing BIM.
4	Cao, Y., & Li, Y. <i>The Study on Design Method of Assembly Structure Based on Computer BIM Technology</i>	The purpose of the paper is to develop a method for assembly structure design using computer-aided BIM technology	The article contains examples of how the design of assembly structure can be carried out using computer-aided BIM technology.		
5	Qiu, S., Xu, H., Jin, J., Zhang, H., & Sun, K. <i>Application of BIM Technology in Construction Engineering</i>	Based on the awareness of the increasing complexity in civil engineering and the inadequacy of traditional safety management tools, the article suggests the need to use BIM Technology as a solution to solve these problems.			

Table 3.7. (continues)Table of 19 articles by PDCA assessment

6	He, L., Xie, Y., & Li, Y. <i>Application and Research of Data Mining Technology BIM and Internet of Things in Engineering Construction</i>	The purpose of the paper is to review the application and research of BIM and IoT technologies in engineering construction.	The article contains examples showing that data mining technology can be used in civil engineering together with BIM and IoT.		The article covers the potential benefits of data mining technology.
7	Lv, M., Zhou, L., Wang, Y., Yang, K., & Yang, C. <i>Summary of BIM Technology Application in a Dormitory Building Project</i>	The purpose of the paper is to present a summary of the application of BIM technology in a dormitory building project.	The article includes examples showing how BIM technology was applied in a student dormitory construction project.		
8	Isikdag, U. <i>The future of building information modelling: BIM 2.0. In Springer Briefs in Computer Science (Vol. 0, pp. 13-24)</i>	The purpose of the paper is to investigate the future of building information modeling (BIM) technology and the potential of BIM 2.0.	The article contains examples discussing various application areas of BIM 2.0.		The article covers the potential benefits of BIM 2.0.

Table 3.7. (continues)Table of 19 articles by PDCA assessment

9	Borrmann, A., König, M., Koch, C., & Beetz, J. <i>Building information modeling: Why? What? How? In Building Information Modeling: Technology Foundations and Industry Practice (pp. 1-24)</i>	The article provides the essential foundational information for implementing BIM and information that can help develop a plan for implementing BIM.	The article contains examples discussing various application areas of BIM.		
10	Svalestuen, F., Knotten, V., Lædre, O., Drevland, F., & Lohne, J. <i>Using Building Information Model (Bim) Devices to Improve Information Flow and Collaboration on Construction Sites</i>	The article provides the essential foundational information for implementing BIM devices on construction sites.	The article includes case studies showing how BIM devices can be used on construction sites.		
11	Heng, L. I., & Hong-Yu, L. I. <i>Applications of BIM in Construction Engineering in China: A Review</i>	The article provides the essential foundational information for implementing BIM in construction engineering in China.	The article contains examples of various projects where BIM has been implemented in China.		

Table 3.7. (continues)Table of 19 articles by PDCA assessment

12	Orace, M. et al. <i>Collaboration in BIM-based Construction Networks: A Bibliometric- Qualitative Literature Review</i>	The article aims to focus on a specific gap, namely the creation of a plan to improve collaboration within BIM-based Construction Networks (BbCNs).	The article conducted real research to implement this strategy.	The article focuses on the stage of checking the results of the implementation phase. This was done by identifying that studies on BIM were technology-focused, but project-related and managerial precursors were missing.	The article represents the phase of planning actions based on the results of the checking phase.
13	Eadie, R. et al. <i>BIM Implementation throughout the UK Construction Project Lifecycle: An Analysis</i>	The article highlights a plan on how to use BIM application at different stages of the construction process.		The article presents several metrics to evaluate and control the results of BIM use.	

Table 3.7. (continues)Table of 19 articles by PDCA assessment

14	Orace, M. et al. <i>Collaboration in BIM-based Construction Networks: A Qualitative Model of Influential Factors</i>		The article aims to modify and validate existing conceptual models. To achieve this, qualitative data was collected and analyzed through semi-structured interviews with BIM experts in the industry.		
15	Li, R., Zhao, H., Wang, X., & Wang, Y. <i>Research on Construction Organization Design and Engineering Cost Application Based on BIM Technology</i>		The article analyzes the state of BIM technology, construction organization design and engineering cost.		
16	Ding, C. <i>Construction Management Mode of Building Engineering Based on BIM Technology</i>	The article discusses the importance of understanding the basic concepts and benefits of BIM, adapting BIM to the needs of the project, and providing the resources and skills necessary to implement BIM.	The article provides examples of how BIM can be used in construction engineering cost management, such as cost estimation, cost control, and cost optimization.		

Table 3.7. (continues)Table of 19 articles by PDCA assessment

17	Wang, N. <i>Research on fine management of engineering cost based on BIM technology</i>	The article includes understanding the basic concepts and benefits of BIM, adapting BIM to the needs of the project, and obtaining the necessary resources and skills to implement BIM.	The article provides a number of case studies that show how BIM can be used in cost management.		
18	Wen, Z. <i>Application Research of BIM Technology in Engineering Cost Management</i>	The article covers understanding the basic concepts and benefits of BIM, adapting BIM according to its achievements, providing the necessary nutrition and recovery to meet the needs of BIM.	The article includes case studies that show how BIM can be used in areas such as cost estimating, cost control and cost optimization.	The article contains methods that can be used to evaluate the effectiveness of BIM in cost management .	
19	Mo, L. <i>Research on Application of BIM Technology in Construction Project Cost Management</i>	The article includes understanding the basic concepts and benefits of BIM, adapting BIM to the needs of the project, providing the necessary resources and skills to implement BIM.	The article includes case studies that show how BIM can be used in areas such as cost estimating, cost control and cost optimization.		

A review of 19 quality-related papers according to the PDCA cycle found that the plan and do stages were more emphasized than the check and act stages. This suggests that the

papers focus on the planning and implementation of quality improvement research, but not enough on the evaluation and implementation of the results of that research.

In the horizontal linear graph you prepared, the x-axis shows the stages of the articles and the y-axis shows the articles. Color-coding the percentage of each stage in the chart makes the data easier to understand. The percentile of the plan phase is shown in blue, the percentile of the do phase is shown in gray, the percentile of the check phase is shown in dark blue, and the percentile of the act phases is shown in light grey.




Figure 3.10. Graph of 19 articles according to PDCA stages (Prepared by Author)

The graph shows that 84% of the 19 articles reviewed were active in the plan and implementation stages, while only 16% were active in the control and action stages (Figure 3.10).

By taking the measures, the effectiveness and efficiency of BIM research can be increased and the adoption and implementation of BIM in the construction industry can be accelerated. Completing the missing article phase using the PDCA cycle will contribute to improving quality by encouraging continuous improvement.

Effectively completing missing stages is crucial for the successful management of a process and continuous improvement. It begins with the identification of deficiencies. Once the missing stages in the process are pinpointed, the next step is to move into the Planning phase. Action plans should be carefully devised, tailored to the nature of the missing stages, and aligned with the goals of the process.

During the Doing phase, the crafted plans need to be executed with precision. The key here is to ensure that the identified actions effectively correct the flow of the process. In the Monitoring phase, the effectiveness of the implemented changes is tracked. Performance data should be regularly evaluated, objectively assessing how successful the process is in achieving the desired outcomes.

If the completion of missing stages does not unfold as planned or if new issues arise, the Checking phase comes into play. This stage involves a detailed analysis of the deficiencies in the process, leading to the development of more effective solutions. This iterative process forms the foundation of continuous improvement, enhancing an organization's adaptability and enabling it to progress on a more solid footing. A review of 19 articles revealed that some aspects were not adequately addressed or new challenges emerged during the application of Building Information Modeling (BIM) in the modular construction sector in the Control and Action phases. The control phase brought to light specific deficiencies in the analyzed processes and revealed examples where initial plans may have been inadequate to effectively correct the flow. This validation serves as an important learning experience that encourages the development of more robust and effective solutions. Moving into the activation phase, adjustments and improvements can be made based on identified deficiencies; This contributes to a more refined and effective use of BIM for quality improvement in modular construction. This iterative process underscores the importance of continuous evaluation, highlighting the adaptation and progress that can be achieved through deliberate changes in BIM implementation strategies.

The meticulous examination of the 19 articles in the context of the PDCA (Plan-Do-Check-Act) cycle has shed light on specific deficiencies in certain phases, necessitating tailored recommendations for improvement.

These findings highlight the importance of a more nuanced approach to the PDCA cycle, emphasizing the need for thoroughness in monitoring and meticulousness in implementing corrective actions. The recommendations serve as a guide for future research endeavors, encouraging a more comprehensive understanding and application of the PDCA cycle in the context of Building Information Modeling (BIM) for quality enhancement in modular construction.

Article 1

Specific recommendations for the check phase

The article presents a strategy developed for the application of BIM technology in construction project management. It is stated that this strategy can increase efficiency, quality and safety during the design, construction and operation phases. The effectiveness of this strategy and what impact it can have on construction projects can be evaluated.

It is stated that the strategy can be used to improve collaboration in the design process, reduce construction errors and increase efficiency. The effectiveness of these uses can be evaluated. It can be evaluated whether the strategy increases communication in the design process, reduces construction errors, and increases efficiency.

Article 2

Specific recommendations for the do phase

The research methodology should be clearly defined. Issues such as the purpose of the research, scope, method, data sources and data analysis methods should be clearly defined. Research data must be collected accurately and completely. Data suitable for the purpose of the research should be collected accurately and completely.

Research results should be reported clearly and understandably. The summary of research results, findings and conclusions should be reported clearly and understandably.

Specific recommendations for the act phase

Research results should be evaluated systematically. Research results should be evaluated systematically to determine whether the objectives of the research have been achieved. Problems and difficulties encountered during the research process should be identified. The research process should be reviewed for problems and difficulties encountered. Lessons should be learned for future research. The results of the research should be analyzed to draw lessons for future research.

Article 3

Specific recommendations for the do phase

Implement the knowledge management strategy suggested in the article. This strategy describes how to collect, manage and share information at different stages of the construction process.

Monitor strategy implementation and make necessary changes. Conduct regular monitoring and evaluation to evaluate the effectiveness and efficiency of the information management strategy.

Specific recommendations for the check phase

Track progress towards achieving the goals of the knowledge management strategy. Monitor this progress using data collected through the monitoring and evaluation system. Use methods such as surveys, interviews, and case studies to evaluate the effectiveness and efficiency of the knowledge management strategy.

Article 4

Specific recommendations for the check phase

In the article, a new method for assembly structure design is proposed. It can be evaluated what advantages this method provides over traditional methods.

The applicability of the method to different types of assembly structures can be evaluated.

The applicability of the method under different project conditions can be evaluated.

Specific recommendations for the act phase

The practical applicability of the method proposed in the article in assembly structure design can be evaluated.

It can be evaluated how the method can be used in education and training in the field of assembly structure design.

How the method can advance research in the field of assembly structure design can be evaluated.

Article 5

Specific recommendations for the do phase

The BIM research mentioned in the article should be reviewed comprehensively.

The use and potential benefits of BIM technology in civil engineering should be evaluated.

The scope and objectives of the research should be determined.

Data collection and analysis methods for the research should be determined.

A timeline and budget should be determined for the research.

Specific recommendations for the check phase

Research results should be analyzed in terms of various factors such as cost, quality, efficiency, information sharing, collaboration, occupational health and safety.

It should be evaluated whether the research results reach the objectives of the research.

Identify problems and challenges encountered during the research process.

Lessons should be learned for future research.

Specific recommendations for the act phase

Based on the research results, recommendations should be developed to improve the use of BIM technology.

Solutions should be proposed to address the challenges encountered.

The future potential of BIM technology should be investigated.

Article 6

Specific recommendations for the check phase

It should be evaluated whether the results obtained in the article are compatible with the existing literature on data mining, BIM and IoT applications in the field of civil engineering.

The data obtained from the construction projects mentioned in the article should be examined and evaluated whether data mining methods extract meaningful information from these data.

Feedback should be sought from civil engineering, data mining, BIM and IoT experts and their opinions about the validity and reliability of the results in the paper.

Article 7

Specific recommendations for the check phase

The effectiveness of the BIM technologies mentioned in the article and their impact on different stages of the construction project can be evaluated. It is stated that BIM technology is used in the design, construction and operation stages of the project. The effectiveness of these uses can be evaluated. It can be evaluated whether BIM technology speeds up the design process, reduces construction errors and reduces operating costs.

Specific recommendations for the act phase

Based on the findings in the article, suggestions can be made for more efficient, high-quality and sustainable use of BIM technology in other construction projects such as dormitory buildings. Recommendations can be made about how BIM technology can be used to improve collaboration in the design process, predict construction errors, and reduce operating costs.

Article 8*Specific recommendations for the check phase*

The article states that BIM models can be used to improve collaboration in the design process, predict construction errors and reduce operating costs. The effectiveness of these uses can be evaluated. It can be evaluated whether BIM models increase communication in the design process, reduce construction errors, and reduce operating costs.

Article 9*Specific recommendations for the check phase*

The article presents a framework that explains the fundamentals and applications of BIM technology. The scope and accuracy of this framework can be evaluated. It can be evaluated whether the framework covers all aspects of BIM technology and whether the information presented is up-to-date.

Specific recommendations for the act phase

Based on the findings in the article, recommendations can be made for understanding and implementing BIM technology. Recommendations can be made for new research that will help us better understand the foundations and applications of BIM technology.

Article 10

Specific recommendations for the check phase

The article offers some suggestions on how BIM devices can be used to improve information flow and collaboration in construction projects. The effectiveness of these recommendations and what impact they may have on construction projects can be evaluated.

It is stated that BIM devices can be used to improve communication, reduce errors and increase efficiency during the design and construction stages. The effectiveness of these uses can be evaluated. It can be evaluated whether BIM devices increase communication in the design process, reduce construction errors, and increase efficiency.

Specific recommendations for the act phase

Based on the findings in the article, suggestions can be made for the more efficient, high-quality and sustainable use of BIM devices in construction projects. Suggestions can be made to make BIM devices more easily accessible and usable by different stakeholders.

Article 11

Specific recommendations for the check phase

The article presents some findings about the scope and effectiveness of BIM applications in China. The accuracy and validity of these findings can be evaluated.

It is stated that BIM applications in China can significantly increase efficiency and quality in the design and construction stages. The accuracy of this finding can be evaluated. It can evaluate how much BIM applications increase efficiency and quality in construction projects in China

Specific recommendations for the act phase

Based on the findings in the article, recommendations can be made for more widespread adoption of BIM applications in China. Can make suggestions for the development of BIM training programs, establishment of BIM standards and dissemination of BIM software.

Article 13*Specific recommendations for the do phase*

More comprehensive research should be conducted to deepen the findings stated in the article. To more clearly understand at which stages of the project life cycle the use of BIM falls, comparative studies can be conducted on different project types and sizes. The distribution of participants in different areas of expertise can be examined, emphasizing the importance of collaboration and process aspects. The reasons for differences in stakeholder financial benefits can be investigated.

The cost effects of BIM use on different stakeholders should be analyzed in more detail. Although the article states that clients derive the most financial benefit from BIM, other stakeholders (contractors, architects, engineers, etc.) can also investigate cost increases or decreases.

The impact of BIM use on project performance should be examined with more project examples.

Specific recommendations for the act phase

Strategies should be developed to expand the use of BIM to all stages of the project life cycle. By understanding the reasons for predominant use in the early stages, education, incentive and collaboration mechanisms can be suggested for later stages. Guidance and standards can be created for project owners to increase 3D model and COBie data set sharing.

Training programs and tools should be developed to improve collaboration and process aspects. Programs can be designed that focus on teamwork, communication, and BIM

integration, as the article reveals that these aspects are more important than software technology.

Training and certification programs should be created to address the lack of BIM expertise. Training providers can develop specific programs for different areas of expertise and skill levels. In close collaboration with industry, practical training focusing on real-world problems can be organized.

Article 14

Specific recommendations for the plan phase

Goals can be set for project managers, such as developing new strategies aimed at increasing collaboration or researching technologies that facilitate knowledge sharing within BbCN.

The needed information can be obtained using new survey studies, case studies, literature review or experiments.

Specific recommendations for the check phase

Collaboration experiences can be collected through surveys from project managers or BbCN members. Examples of collaboration in different projects can be examined through case studies.

It should uncover the factors that have the greatest impact on collaboration and consider different perspectives (management, team members, technology, etc.).

Evaluate how much the research contributes to the goals of improving collaboration or closing relevant knowledge gaps.

Specific recommendations for the act phase

Based on the research results, strategies should be developed to improve BbCN collaboration. These strategies can cover a variety of areas, such as project management

techniques, communication protocols, information sharing platforms, training programs and technology applications.

Support research focusing on topics such as the impact of extra-project factors (sociological, cultural, etc.) on collaboration or optimization of team dynamics.

The information obtained should be transferred to project management applications. It may be useful to develop BbCN creation guides, collaboration evaluation tools, or training modules.

Article 15

Specific recommendations for the plan phase

The impact of BIM technology on cost and organizational design should be examined comparatively with different types of projects such as commercial buildings and infrastructure projects, as well as other types of construction projects.

By using BIM technology, one can aim to achieve a certain cost saving rate or increase the efficiency in the project organization by 20%.

In addition to the data in the article, BIM application data from different projects, survey results or case studies from project managers and BIM experts can be analyzed.

Specific recommendations for the check phase

Examine the change in cost and organizational design with the use of BIM for different project types. The effects of BIM use in project stages should be analyzed.

The impact of BIM technology on cost and organizational design should be quantified. It should be examined how different factors (BIM expertise, project complexity, software, etc.) affect this effect.

You should evaluate how successful your research is in achieving the targeted cost savings or organizational efficiency increase.

Specific recommendations for the act phase

New methodologies, BIM-compatible organizational structures, or BIM applications integrated into the project calendar can be designed that take into account the use of BIM in project budgeting.

Needs for future research should be determined by addressing limitations such as limited research scope and lack of data.

Research results should be reflected in project management guides, training programs and BIM application standards. Training materials highlighting the cost and organizational benefits of BIM technology should be prepared for industry stakeholders.

Article 16

Specific recommendations for the check phase

Although the article has examined the impact of the BIM model on project cost management, it is also useful to consider the impact of BIM technology on other aspects of the construction management mode. The impact of BIM on project organization, quality control, collaboration and communication can also be examined.

The article states that the BIM model can dynamically reflect cost changes. However, the quantitative analysis of these changes and their net impact on the project cost should be revealed in more detail. Changes in different cost items (material, labor, equipment, etc.) should be examined separately.

It should be analyzed whether you have achieved the objectives set at the beginning of your research (e.g. cost savings rate, increased effectiveness in cost control).

Specific recommendations for the act phase

Based on the research results, strategies should be developed to increase the contribution of the BIM model to project cost management.

If there are difficulties, data deficiencies or technological limitations in the use of BIM revealed in the research, solutions should be proposed to resolve them.

Research results should be reflected in project management guides, BIM application standards and training materials. Resources can be prepared that emphasize the benefits of BIM technology in terms of project cost management and include practical examples.

Article 17*Specific recommendations for the check phase*

The impact of BIM technology on other project performance criteria such as project time, quality and protection from work accidents should be examined.

The impact of BIM technology on different project types, sizes and complexities should be examined.

The impact of BIM technology on project cost management should be analyzed quantitatively.

Specific recommendations for the act phase

Cost estimation and control tools integrated with the BIM model should be developed.

Training programs and consultancy services to increase BIM expertise should be offered.

Resources that emphasize the benefits of BIM technology in terms of project cost management and include practical examples should be prepared.

Article 18

Specific recommendations for the act phase

The effectiveness of BIM-based cost management methods may vary depending on the complexity and size of the project. It should be evaluated whether the methods are suitable for a particular project or need to be adapted.

BIM-based cost management methods can be applied in different ways at different stages of the project. It should be evaluated how the methods are applied at each stage and whether the application encounters any problems or difficulties.

BIM-based cost management methods can be used in different ways by different stakeholders of the project. How the methods are used by different stakeholders and the level of satisfaction with use should be evaluated.

Article 19

Specific recommendations for the check phase

Cost management shortcomings of other types of construction projects (infrastructure, industrial, commercial, etc.) should also be examined.

Although the article states that BIM technology provides cost savings, it would be useful to clearly state the rate of this saving and in which cost items it occurs.

If the use of BIM aims to achieve a certain cost savings rate, reduce cost deviations at a certain rate, or improve cost control processes in a certain way, it should be analyzed to what extent these goals have been achieved.

Specific recommendations for the act phase

More advanced cost estimation algorithms, cost control tools integrated with the BIM model, or real-time cost monitoring systems can be applied.

Choose software with high BIM compatibility. BIM training and consultancy services should be provided or BIM application guides should be prepared for project owners.

Resources can be prepared that emphasize the benefits of BIM technology in terms of cost control management and include practical examples.

The highlighted areas in the paragraph represent potential gaps or deficiencies within the articles that, when addressed, would signify the completion of the Plan-Do-Check-Act (PDCA) cycle. These gaps serve as opportunities for continuous improvement and refinement in the application of Building Information Modeling (BIM) within the context of modular construction.

Table 3.8. Table consisting of 19 articles according to common results from the PDCA evaluation

Task	Article	Description
Plan	15 & 16	Compare BIM impact on cost and organization across different project types.
Plan	14	Set project manager goals for BbCN collaboration improvements and research knowledge-sharing technologies.
Do	3 & 13	Implement and monitor the proposed knowledge management strategies.
Do	5	Conduct comprehensive BIM research in civil engineering.
Do	13	Conduct deeper research on BIM use stages, collaboration aspects, and stakeholder financial benefits.
Check	1, 2, 7, 8, 10	Evaluate the effectiveness of proposed strategies or BIM applications on project aspects like efficiency, quality, and cost.
Check	4, 6, 9, 11, 12	Evaluate the scope, accuracy, and validity of presented frameworks, findings, and data.
Check	13, 14, 15, 16, 19	Quantify the impact of BIM on various project aspects like cost, collaboration, and organizational design.
Check	16 & 17	Analyze the impact of BIM on cost changes and other performance criteria like time, quality, and safety.
Act	1, 7, 10	Develop strategies for wider BIM adoption based on findings.
Act	2, 5, 13	Address research limitations and suggest future research directions.
Act	3, 14	Create training programs and tools to improve collaboration and process aspects.
Act	11, 15, 19	Develop recommendations for wider BIM adoption, training programs, and BIM application standards.
Act	16, 17, 18	Design tools, training programs, and resources to enhance BIM-based cost management.

In the planning phase, the identified gaps might include the need for a more detailed articulation of the project goals in Articles 15 and 16. Clearer and more specific objectives could enhance the overall planning process, aligning it more closely with the principles of the PDCA cycle.

Moving to the execution phase, the implementation and monitoring of knowledge management strategies in Articles 3 and 13 could benefit from a more detailed account of the execution process. Providing a comprehensive overview of how these strategies were implemented and monitored would strengthen the execution phase.

Article 5, focusing on conducting comprehensive BIM research in civil engineering, could potentially have gaps related to the depth and breadth of the research. Identifying specific areas within civil engineering where BIM applications are most impactful would further enhance the execution phase.

The deeper research conducted in Article 13 might highlight gaps in the current understanding of BIM use stages, collaboration aspects, and stakeholder financial benefits. Addressing these gaps would contribute significantly to the completion of the PDCA cycle.

The evaluation activities in the checking phase, particularly in Articles 1, 2, 7, 8, and 10, may reveal gaps in the assessment criteria or in the data collected for evaluation. A more thorough examination of these aspects would strengthen the checking phase.

Articles 4, 6, 9, 11, and 12, evaluating the scope, accuracy, and validity of frameworks and findings, could potentially identify gaps in the methodologies employed for evaluation. Addressing these gaps would contribute to the completeness of the checking phase.

In the acting phase, the development of strategies for wider BIM adoption (Articles 1, 7, 10) might reveal gaps in the proposed strategies or areas where additional refinement is needed. Addressing these gaps ensures a more effective implementation of the actions.

Articles 2, 5, and 13, addressing research limitations and suggesting future research directions, could potentially highlight gaps in the current understanding of BIM

applications in modular construction. Filling these gaps would signify a commitment to ongoing improvement.

The creation of training programs and tools to improve collaboration and process aspects (Article 3, 14) might uncover gaps in the practical implementation of these programs. Addressing these gaps would contribute to the continuous improvement of collaboration processes.

Articles 11, 15, 19, focusing on developing recommendations for wider BIM adoption, training programs, and BIM application standards, could potentially identify gaps in the practicality or feasibility of these recommendations. Closing these gaps ensures a more robust and actionable set of recommendations.

In the design of tools, training programs, and resources to enhance BIM-based cost management (Articles 16, 17, 18), potential gaps might include areas where the designed tools need further refinement. Addressing these gaps completes the PDCA cycle, ensuring a continuous loop of improvement.

Paying equal attention to all stages of the PDCA cycle will make quality-related research more effective and efficient. Based on 19 articles, it is clearly seen that the general deficiency in these articles is in the check and act stages. While the reviewed 19 articles offer valuable insights into BIM and modular construction's potential for quality improvement, many lack complete "check" and "act" sections within the PDCA cycle. By closing the gaps in the PDCA cycle and embracing these practices, researchers can transform BIM and modular construction from promising concepts into proven quality engines for the construction industry. This commitment to rigorous evaluation and continuous improvement will pave the way for a future where quality is not just aspired to but systematically achieved through the power of integrated technologies and data-driven insights.

In conclusion, by recognizing and actively addressing these potential gaps, the articles would demonstrate a commitment to the iterative nature of the PDCA cycle, marking the completion of each phase and setting the stage for ongoing improvement in the application of BIM in modular construction.

4. CONCLUSION

In the rapidly evolving field of construction management, the integration of innovative technologies has become pivotal for achieving efficiency and quality in project execution. This study investigates the potential of BIM to enhance quality in the realm of modular construction, examining six hypotheses and their corresponding sub-research questions. Through our analysis, we have obtained answers to each sub-research question, validating the main objectives of the study. Firstly, it is evident that the use of BIM improves efficiency and reduces delays in modular construction projects. This is facilitated by BIM tools that streamline communication, coordination, and project monitoring processes. Additionally, BIM demonstrates positive impacts on expenditure control and logistics management in modular construction projects. The visualization of project data and enhanced collaboration among stakeholders provided by BIM offer better cost tracking and logistical planning capabilities.

Furthermore, it has been determined that the implementation of BIM significantly enhances communication and information management in modular construction. Sharing project data on a central platform facilitates real-time collaboration and integration of various project information, organizing information flow throughout the project lifecycle. Additionally, examining BIM and modular construction holistically is crucial for ensuring quality management. Considering the entire project lifecycle from design to construction and operation, BIM supports informed decision-making, fosters collaboration among project teams, and ensures consistency and continuity throughout project phases.

Collaboration and stakeholder engagement have also been found to play a significant role in BIM and modular construction projects. Efforts to promote collaboration among stakeholders, facilitate open communication, and actively involve stakeholders throughout the project lifecycle are essential for project success and quality improvement.

Lastly, the study explores how the impact of BIM on cost management can be measured. By using various metrics such as cost savings, reduced cost overruns, and improved accuracy in cost estimation, the effectiveness of BIM in cost management can be assessed. Analyzing project data and comparing cost performance metrics between BIM-supported

and traditional construction projects provide insights into BIM's effectiveness in cost savings and enhancing cost management practices in the modular construction industry.

These findings underscore the potential of BIM and modular construction in enhancing quality and highlight the critical role of these technologies in driving continuous improvements in the construction industry.

Through the investigation of six hypotheses and their corresponding sub-research questions, we navigated the complexities of BIM implementation and its impact on various facets of project management. Notably, the examination of 19 articles within the PDCA (Plan-Do-Check-Act) cycle shed light on both successes and areas for improvement in integrating BIM into modular construction practices. By adopting the PDCA cycle, the thesis aims not only to understand the impact of BIM on various project types but also to systematically improve its application in the context of modular construction systems.

The comparative analysis conducted in the thesis assesses how BIM influences different project types, shedding light on its varied implications across the construction sector. By focusing on modular construction systems, the research addresses a specific niche within the broader construction landscape, offering insights into the unique challenges and opportunities presented by modular projects.

One notable aspect of the thesis is its proactive approach to continuous improvement within the PDCA cycle. By identifying gaps and needs in the existing literature and BIM practices, the thesis lays the groundwork for ongoing refinement. This emphasis on addressing shortcomings and adapting strategies distinguishes the research, positioning it not only as an analysis of the current state but as a catalyst for future advancements in BIM applications.

Moreover, the acknowledgment of the gaps in the research literature serves as an important contribution. The thesis recognizes the need for further exploration and empirical evidence, particularly in the synergy between BIM and modular construction concerning construction quality. This recognition of a gap in existing knowledge is crucial, as it not only highlights areas for potential improvement but also suggests opportunities for future research endeavors.

Despite the potential synergy between BIM and modular construction in enhancing construction quality, the thesis points out a lack of direct evidence in the 19 selected articles supporting this hypothesis. This observation emphasizes the importance of conducting additional research to delve deeper into the specific benefits and tangible evidence of utilizing BIM and modular construction in tandem. By doing so, the research not only identifies a gap in the current literature but also advocates for a more comprehensive understanding through empirical studies, contributing to the academic and practical knowledge in this field.

4.1. Discussion of Enhancing Modular Construction Quality through BIM

This study provides a comprehensive discussion on the deficiencies observed in the 'check' and 'act' stages of the PDCA cycle, as well as broader considerations stemming from these identified shortcomings, by examining the potential of Building Information Modeling (BIM) and modular construction in enhancing quality. A fundamental observation arising from the reviewed literature is the inevitable necessity for a more robust and comprehensive approach to quality measurement within the context of BIM and modular construction. While the analyzed articles offer valuable insights into the potential benefits of these technologies for improving project quality, the absence of concrete and standardized metrics poses a significant limitation. Researchers must emphasize the development and implementation of standardized defect tracking systems to address this gap. This holistic approach enables a deeper understanding of the impact of BIM and modular construction on project quality, facilitating evidence-based decision-making in project planning and execution.

A fundamental observation arising from the reviewed literature is the imperative need for a more robust and comprehensive approach to quality measurement within the context of Building Information Modeling (BIM) and modular construction. While the analyzed articles provide valuable insights into the potential benefits of these technologies for enhancing project quality, the absence of concrete and standardized metrics poses a significant limitation. Researchers must emphasize the development and implementation of standardized defect tracking systems, as well as the integration of BIM-derived data into quality assessment processes. This holistic approach enables a more thorough understanding of the impact of BIM and modular construction on project quality and

facilitates more accurate comparisons between different construction methodologies, thereby informing evidence-based decision-making in project planning and execution.

Furthermore, the significance of conducting comparative analyses to evaluate the effectiveness of BIM and modular construction techniques cannot be overstated. By comparing projects employing these innovative methodologies with those utilizing traditional approaches, researchers can establish baseline performance metrics and assess the relative advantages and disadvantages of each method. Such comparative analyses allow for a nuanced understanding of the specific contributions of BIM and modular construction to overall project quality, thereby highlighting areas for improvement and informing future research and implementation strategies.

In addition to quantitative analyses, qualitative insights derived from focus group discussions with project stakeholders offer invaluable perspectives on the practical implications of BIM and modular construction technologies. By capturing stakeholders' subjective experiences and perceptions, researchers can gain deeper insights into the real-world impacts of these technologies and identify potential barriers to their adoption and implementation. Qualitative data complement quantitative analyses by providing context and nuance, enriching the overall understanding of the complex interplay between technology, processes, and project outcomes.

Moreover, the importance of targeted quality improvements cannot be overstated in driving meaningful change in construction practices. Building upon the findings from the "check" phase of the PDCA cycle, researchers must develop tailored interventions and strategies to address identified deficiencies and enhance overall project quality. This may involve the development of BIM-specific quality control procedures, optimization of modular construction processes, and the implementation of industry-wide training programs to promote best practices in quality management and assurance.

Lastly, the discussion emphasizes the iterative nature of the PDCA cycle and the importance of continuous improvement in driving advancements in BIM and modular construction. By actively soliciting feedback, refining measurement methods, and adapting interventions based on evolving project contexts and technological advancements,

researchers can ensure that their findings remain relevant and impactful in addressing the ever-changing challenges of the construction industry.

In summary, the discussion section underscores the critical role of the PDCA cycle in guiding future research and practical implementations in the realm of BIM and modular construction. By addressing the identified deficiencies and embracing the recommended practices, researchers can drive systematic and sustained improvements in project quality and performance, ultimately contributing to the advancement of the construction industry as a whole.

4.2. Future Research Areas

This thesis serves as a catalyst for future research endeavors aimed at further enhancing the quality of modular construction through the integration of Building Information Modeling (BIM). The proposed Plan-Do-Check-Act (PDCA) cycle not only provides a systematic framework for current investigations but also paves the way for future explorations focused on elevating the quality standards within modular construction practices.

Future research should rigorously employ a multi-pronged approach, drawing from quantitative and qualitative methods within the PDCA cycle. Robust quality metrics, encompassing various aspects like defect rates, client satisfaction, and project performance, coupled with comparative analyses against traditional methods, can establish a baseline for impact assessment. Further, in-depth qualitative measures like focus group discussions with project stakeholders can offer valuable insights into perceived quality changes. The "Act" phase of the cycle plays a crucial role in solidifying these findings. Implementing targeted quality improvements informed by the "Check" phase, such as refined BIM model quality control procedures or dedicated modularity training programs, can demonstrably enhance quality outcomes. By continuously iterating through this cycle and refining both the measurement and improvement strategies, a compelling body of evidence can be built to solidify the claim of BIM and modular construction's impact on quality. This data-driven approach, coupled with ongoing innovation and optimization, paves the way for a future where these integrated practices become synonymous with quality in the construction industry.

One avenue for future research lies in the in-depth examination of how BIM applications can specifically contribute to improving the quality aspects of modular construction projects. Investigating the impact of BIM on precision, accuracy, and consistency in the manufacturing and assembly of modular components could offer valuable insights into optimizing quality control processes.

Furthermore, exploring advancements in BIM technologies and methodologies tailored to modular construction will be crucial. Future studies might delve into refining parametric modeling for increased customization within standardized sizes, enhancing clash detection algorithms to prevent errors during design coordination, and developing real-time collaboration tools that streamline communication and decision-making processes.

The integration of artificial intelligence and machine learning into BIM for modular construction represents another promising avenue. Understanding how these technologies can predict and prevent quality-related issues, optimize material selection for enhanced durability, and facilitate real-time quality assurance will be instrumental in shaping the future of modular construction.

Additionally, future research could focus on assessing the long-term quality implications of BIM adoption in modular construction projects. Investigating the lifecycle performance of structures designed and constructed using BIM could provide valuable data on the durability, resilience, and overall quality of modular buildings over time.

Moreover, qualitative research can be employed to explore the perceptions of project stakeholders, including architects, engineers, contractors, and end-users, regarding the perceived quality improvements facilitated by the combined use of BIM and modular construction. Such studies would contribute to a comprehensive understanding of the multifaceted dimensions of quality within the context of these advanced construction methodologies. Overall, a holistic and multidimensional research approach is essential to substantiate and generalize the positive impacts of BIM and modular construction on construction quality.

As the construction industry continues to evolve, this thesis encourages researchers to delve into these quality-centric aspects, fostering a continuous cycle of inquiry and

improvement. By addressing these future research areas, we can collectively contribute to a more robust understanding of how BIM can significantly elevate the quality standards within the realm of modular construction.

In conclusion, this thesis provides valuable insights into the intersection of BIM and modular construction, offering a roadmap for further research and practical implementation. The comprehensive analysis, focus on continuous improvement, and identification of gaps contribute to the ongoing discourse on optimizing construction processes through advanced technologies.

REFERENCES

1. Yan, M. (2015). Project-Based Market Competition and Policy Implications for Sustainable Developments in Building and Construction Sectors. *Sustainability*, 7, 15423-15448.
2. Olawumi, T. O., Chan, D. W. (2018). Identifying and prioritizing the benefits of integrating BIM and sustainability practices in construction projects: A Delphi survey of international experts. *Sustainable Cities and Society*, 40, 16-27.
3. Mellado, F., Lou, E. C. (2020). Building information modelling, lean and sustainability: An integration framework to promote performance improvements in the construction industry. *Sustainable cities and society*, 61, 102355.
4. McHugh, K., Dave, B., Craig, R. (2019). Integrated lean and BIM processes for modularised construction-A case study. In *27th Annual conference of the international group for lean construction, IGLC*, 201 (9), 227-238.
5. Fotouh, S., Ezeldin, A. (2019). Cost Optimization Of Multiple Resources Allocation For Multi-Projects. *Proceedings of International Structural Engineering and Construction*. <https://doi.org/10.14455/isec.res.2019.52>.
6. Yi, L. (2020). Research and Analysis of Fine Management of Engineering Cost Based on BIM. In *Artificial Intelligence and Security: 6th International Conference, ICAIS Hohhot, China, July Proceedings, Part I* 6, 496-502.
7. Ocheoha, I., Moselhi, O. (2018). A BIM-based Supply Chain Integration for Prefabrication and Modularization. <https://doi.org/10.29173/MOCS35>.
8. Ma, Z., Cai, S., Mao, N., Yang, Q., Feng, J., Wang, P. (2018). Construction quality management based on a collaborative system using BIM and indoor positioning. *Automation in Construction*, 92, 35-45.
9. Lin, Y., Chang, J., Su, Y. (2016). Developing Construction Defect Management System Using BIM Technology In Quality Inspection. *Journal of Civil Engineering and Management*, 22, 903-914.
10. Elsheikh, A., Alamedy, S. (2023). Relate Building Information Modeling To Quality Management According To The Different Quality Management Phases. *IOP Conference Series: Earth and Environmental Science*, 1129.
11. Elsheikh, A., Alamedy, S. G. H. (2023). Relate building information modeling to quality management according to the different quality management phases. In *IOP Conference Series: Earth and Environmental Science*, 1129 (1), 012043.
12. Won, J., Cheng, J. (2017). Identifying Potential Opportunities Of Building Information Modeling For Construction And Demolition Waste Management And Minimization. *Automation in Construction*, 79, 3-18.

13. Becerik-Gerber, B., Kensek, K. (2010). Building Information Modeling in Architecture, Engineering, and Construction: Emerging Research Directions and Trends. *Journal of Professional Issues in Engineering Education and Practice*, 136, 139-147.
14. Doumbouya, L., Gao, G., Guan, C. (2016). Adoption of the Building Information Modeling (BIM) for Construction Project Effectiveness: The Review of BIM Benefits. *American Journal of Civil Engineering and Architecture*, 4, 74-79.
15. Mustaffa, N., Salleh, R., Ariffin, H. (2017). Experiences of Building Information Modelling (BIM) adoption in various countries. *International Conference on Research and Innovation in Information Systems (ICRIIS)*, 1-7.
16. Sampaio, A., Sequeira, P., Gomes, A., Sánchez-Lite, A. (2022). BIM Methodology in Structural Design: A Practical Case of Collaboration, Coordination, and Integration. *Buildings*. 13(1), 31.
17. Alaloul, W., Qureshi, A., En, Y., Khan, S., Musarat, M., Alzubi, K., Salaheen, M. (2023). Survey Evaluation of Building Information Modelling (BIM) for Health and Safety in Building Construction Projects in Malaysia. *Sustainability*. 15(6), 4899.
18. Famakin, I., Othman, I., Kineber, A., Oke, A., Olanrewaju, O., Hamed, M., Olayemi, T. (2023). Building Information Modeling Execution Drivers for Sustainable Building Developments. *Sustainability*. 15(4), 3445.
19. Kineber, A., Massoud, M., Hamed, M., Alhammadi, Y., Al-Mhdawi, M. (2023). Impact of Overcoming BIM Implementation Barriers on Sustainable Building Project Success: A PLS-SEM Approach. *Buildings*. 13(1), 178.
20. Chen, Y., Wang, X., Liu, Z., Cui, J., Osmani, M., Demian, P. (2023). Exploring Building Information Modeling (BIM) and Internet of Things (IoT) Integration for Sustainable Building. *Buildings*. 13(2), 288.
21. Sarvari, H., Chan, D., Rakhshanifar, M., Banaitienė, N., Banaitis, A. (2020). Evaluating the Impact of Building Information Modeling (BIM) on Mass House Building Projects. *Buildings*. 10(2), 35.
22. Almashaqbeh, M., El-Rayes, K. (2021). Minimizing transportation cost of prefabricated modules in modular construction projects. *Engineering, Construction and Architectural Management*. 29(10), 3847-3867.
23. Tavares, V., Soares, N., Raposo, N., Marques, P., Freire, F. (2021). Prefabricated versus conventional construction: Comparing life-cycle impacts of alternative structural materials. *Journal of Building Engineering*, 41, 102705.
24. Azhar, S. (2011). Building Information Modeling (BIM): Trends, Benefits, Risks, and Challenges for the AEC Industry. *Leadership and Management in Engineering*, 11, 241-252.

25. Naticchia, B., Corneli, A., Carbonari, A. (2020). Framework based on building information modeling, mixed reality, and a cloud platform to support information flow in facility management. *Frontiers of Engineering Management*, 7, 131-141.
26. Zarzycki, A. (2011). Designing with constraints parametric BIM. In *ACM SIGGRAPH 2 Talks*, 1-1.
27. Cheng, Y. M., Wu, I. C. (2013). Parametric BIM objects exchange and sharing between heterogeneous BIM systems. In *ISARC. Proceedings of the International Symposium on Automation and Robotics in Construction*, .329-336.
28. Haukaas, T., Gavrilovic, S. (2017). A Computational Framework For Holistic Life-Cycle *Design Of Buildings*. 4.
29. Pocobelli, D., Boehm, J., Bryan, P., Still, J., Grau-Bové, J. (2018). BIM for heritage science: a review. *Heritage Science*, 6, 1-15.
30. Gamayunova, O., Vatin, N. (2014). BIM-Technology in Architectural Design. *Advanced Materials Research*, 1065-1069, 2611 - 2614.
31. Zarzycki, A. (2010). Exploring parametric BIM as a conceptual tool for design and building technology teaching. In *Proceedings of the Spring Simulation Multiconference*, 194.
32. Amoaha, E. K., Nguyenb, T. V. (2019). Optimizing the usage of Building Information Model (BIM) interoperability focusing on data not tools. In *ISARC. Proceedings of the International Symposium on Automation and Robotics in Construction*, 36, 1081-1090.
33. Kim, J., Ock, J. (2009). A Study on the Development of the Problem Improvement Directions in Enhancing BIM Data Interoperability through IFC. *Korean Journal of Construction Engineering and Management*, 10, 88-98.
34. Paik, S., Leviakangas, P., Choi, J. (2020). Making most of BIM in design: analysis of the importance of design coordination. *International Journal of Construction Management*, 22, 2225 - 2233.
35. Park, G., Jung, Y., Ham, N., Kim, J. (2013). A Study of the Using Application Program Interface (API) for Improving Productivity in Construction *Engineering*. 3, 29-38.
36. Bhuskade, S. (2015). Building Information Modeling (BIM) New Era In Indian Senario. <https://doi.org/10.21090/ijaerd.0205153>.
37. Kalutara, P., London, K., Taylor, C. (2021). Significance of a software interoperability matrix for architectural engineering and construction industry. *Journal Of Information Technology In Construction.*, 26, 739-757.

38. Azevedo, G. F. (2022). BIM methodology implementation in structural design: Adaptation of procedures and information management. *Journal of Civil Engineering and Environmental Sciences*, 8(1), 093-099.
39. Florez, L., Afsari, K. (2018). *Integrating Facility Management Information into Building Information Modelling using COBie: Current Status and Future Directions*. Proceedings of the 35th International Symposium on Automation and Robotics in Construction (ISARC). <https://doi.org/10.22260/isarc2018/0116>.
40. Soust-Verdaguer, B., Moreno, J., Llatas, C. (2023). Utilization of an Automatic Tool for Building Material Selection by Integrating Life Cycle Sustainability Assessment in the Early Design Stages in BIM. *Sustainability*, 15(3), 2274.
41. Waqar, A., Qureshi, A., Alaloul, W. (2023). Barriers to Building Information Modeling (BIM) Deployment in Small Construction Projects: Malaysian Construction Industry. *Sustainability*, 15(3), 2477.
42. Paparella, R., Caini, M. (2018). Innovative Approach to the Configuration of Smart Buildings. *IN_BO. Ricerche e progetti per il territorio, la città e l'architettura*, 9(13), 52-63.
43. Gunawardena, T., Mendis, P. (2022). Prefabricated building systems—design and construction. *Encyclopedia*, 2(1), 70-95.
44. Liew, J. Y. R., Chua, Y. S., Dai, Z. (2019, October). Steel concrete composite systems for modular construction of high-rise buildings. *In Structures* 21, 135-149. Elsevier.
45. Mohammadi, A., Igwe, C., Amador-Jimenez, L., Nasiri, F. (2020). Applying lean construction principles in road maintenance planning and scheduling. *International Journal of Construction Management*, 22, 2364 - 2374.
46. Chen, R. (2014). An Integrated Sustainable Business and Development System: Thoughts and Opinions. *Sustainability*, 6, 6862-6871.
47. Lienhard, J., Poppinga, S., Schleicher, S., Speck, T., Knippers, J. (2010). Elastic architecture: nature inspired pliable structures. *Design and Nature*, 138, 469-477.
48. Nath, A. S. (2022). A Review of Advancements in Robotic and Sensor-based Technologies in Construction Sector. *European Journal of Engineering and Technology Research*, 7(1), 85-89.
49. Mohsen, O. M., Knytl, P. J., Abdulaal, B., Olearczyk, J., Al-Hussein, M. (2008, December). Simulation of modular building construction. In , *Winter Simulation Conference*, 2471-2478.
50. Liew, J. Y. R., Chua, Y. S., Dai, Z. (2019). Steel concrete composite systems for modular construction of high-rise buildings. *In Structures*, 21, 135-149.

51. Sultana, P., Youssef, M. (2020). Seismic Performance of Modular Steel-Braced Frames Utilizing Superelastic Shape Memory Alloy Bolts in the Vertical Module Connections. *Journal of Earthquake Engineering*, 24, 628 - 652.
52. Hussamadin, R., Jansson, G., Mukkavaara, J. (2023). Digital Quality Control System—A Tool for Reliable On-Site Inspection and Documentation. *Buildings*, 13(2), 358.
53. Ahn, Y., Kim, K. (2014). Sustainability in modular design and construction: a case study of ‘The Stack’. *International Journal of Sustainable Building Technology and Urban Development*, 5, 250-259.
54. Enright, J., Jilla, C., Miller, D. (1998). Modularity and Spacecraft Cost. *Journal of Reducing Space Mission Cost*, 1, 133-158.
55. Lin, C., Lai, Y. (2020). An Improved Time-Cost Trade-Off Model With Optimal Labor Productivity. *Journal of Civil Engineering and Management*, 26, 113-130.
56. Tugilimana, A., Coelho, R., Thrall, A. (2019). An integrated design methodology for modular trusses including dynamic grouping, module spatial orientation, and topology optimization. *Structural and Multidisciplinary Optimization*, 1-26.
57. Dong, C., Wang, H., Zhang, H., Zhang, M., Guan, J., Zhang, Z., Zuo, Z. (2022). Research on Fine Scheduling and Assembly Planning of Modular Integrated Building: A Case Study of the Baguang International Hotel Project. *Buildings*, 12(11), 1892.
58. Lu, N., Korman, T. (2010). Implementation of Building Information Modeling (BIM) in Modular Construction: *Benefits and Challenges*, 1136-1145.
59. Panteli, C., Kylili, A., Fokaides, P. (2020). Building information modelling applications in smart buildings: From design to commissioning and beyond A critical review. *Journal of Cleaner Production*, 265, 121766.
60. Liu, H., Wang, G., Zhang, L. (2013). Research on BIM-Based Construction Project Organization Interface Management. *Applied Mechanics and Materials*, 357-360, 2781-2784.
61. Kim, D., Lee, S., Kim, S. A. (2012). A visualization system for the comfort analysis of modular architecture: a case study. In *Cooperative Design, Visualization, and Engineering: 9th International Conference, CDVE 2012, Osaka, Japan, September 2-5, Proceedings 9*, 247-254.
62. Signorini, M., Spagnolo, S. (2021). Building Renovation Process Map in Private and Public Works to Improve Communication and Data Exchange. *IOP Conference Series: Materials Science and Engineering*, 1044.
63. Salem, O., Samuel, I. J., He, S. (2020). Bim And Vr/Ar Technologies: From Project Development To Lifecycle Asset Management. *Proceedings of the International Structural Engineering and Construction, Angamaly, India*, 14-15.

64. Al-Taie, A. (2016). Estimation of Project Duration and Cost Using Building Information Modeling (BIM). *International Journal of Research*, 3, 301-318.
65. Mutis, I., Paramashivam, A. (2019). Cybersecurity management framework for a cloud-based BIM model. In *Advances in Informatics and Computing in Civil and Construction Engineering: Proceedings of the 35th CIB W78 2018 Conference: IT in Design, Construction, and Management*, 325-333.
66. Muratova, A., Ptukhina, I. (2019). BIM as an Instrument of a Conceptual Project Cost Estimation, 469-477.
67. Muratova, A., Ptukhina, I. (2019, November). BIM as an instrument of a conceptual project cost estimation. In *International Scientific Conference on Energy, Environmental and Construction Engineering*, 469-477.
68. Lianguang, M. (2016). Study on Project Information Management Based on Building Information Modeling. 2016 *International Conference on Smart City and Systems Engineering (ICSCSE)*, 238-240.
69. Tsoupra, A., Tsoukalis, F., Chassiakos, A. (2019). BIM-Based Risk Identification and Assessment in Building Projects at their design Phase. . <https://doi.org/10.33107/UBT-IC.2019.184>.
70. Murphy, M., Nahod, M. (2017). Stakeholder competency in evaluating the environmental impacts of infrastructure projects using BIM. *Engineering, Construction and Architectural Management*, 24, 718-735.
71. Dossick, C. S., Neff, G., Homayouni, H. (2009). The realities of building information modeling for collaboration in the AEC industry. In *Construction Research Congress 2009: Building a Sustainable Future*, 396-405.
72. Barlish, K., Sullivan, K. (2012). How To Measure the Benefits of BIM - A Case Study Approach. *Automation in Construction*, 24, 149-159.
73. Ershadi, M., Jefferies, M., Davis, P., Mojtahedi, M. (2021). A Building Information Modelling (BIM) Approach to the Systematic Management of Construction Projects. IOP Conference Series: *Materials Science and Engineering*, 1165.
74. Jiang, Y., Ma, P., Zhang, S. (2018). Contractual governance of BIM-enabled projects: Where are we. *International Journal of Architecture, Engineering and Construction*, 7(1), 1-10.
75. Oh, M., Lee, J., Hong, S., Jeong, Y. (2015). Integrated system for BIM-based collaborative design. *Automation in Construction*, 58, 196-206.
76. Zeng, X., Tan, J. (2007). Building information modeling based on intelligent parametric technology. *Frontiers of Architecture and Civil Engineering in China*, 1, 367-370.

77. Baroš, T. (2016). The Application Of Bim Technology And Its Reliability In The Static Load Analysis. *Tehnicki vjesnik/Technical Gazette*, 23(4).3-5.
78. Banihashemi, S., Tabadkani, A., Hosseini, M. (2018). Integration of parametric design into modular coordination: A construction waste reduction workflow. *Automation in Construction*, 88, 1-12.
79. He, R., Li, M., Gan, V. J., Ma, J. (2021). BIM-enabled computerized design and digital fabrication of industrialized buildings: A case study. *Journal of Cleaner Production*, 278, 123505.
80. Rybakova, A. (2022). Evaluating the efficiency of modular design based on prefabricated elements. *Stroitel'stvo: nauka i obrazovanie*, Construction: Science and Education. <https://doi.org/10.22227/2305-5502.2022.3.9>.
81. Chahrour, R., Hafeez, M., Ahmad, A., Sulieman, H., Dawood, H., Rodriguez-Trejo, S., Kassem, M., Naji, K., Dawood, N. (2020). Cost-benefit analysis of BIM-enabled design clash detection and resolution. *Construction Management and Economics*, 39, 55-72.
82. Ramaji, I. J., Memari, A. M. (2015). Information exchange standardization for BIM application to multi-story modular residential buildings. In *AEI*, 13-24.
83. Alsayyar, B., Jrade, A. (2015). Integrating building information modeling (BIM) with sustainable universal design strategies to evaluate the costs and benefits of building.
84. Zaini, N., Zaini, A. A., Tamjehi, S. D., Razali, A. W., Gui, H. C. (2020). Implementation of building information modeling (BIM) in sarawak construction industry: a review. In *IOP Conference Series: Earth and Environmental Science*, 498(1), 012091.
85. Preidel, C., Borrmann, A., Mattern, H., König, M., Schapke, S. (2021). Common Data Environment. Building Information Modeling. https://doi.org/10.1007/978-3-319-92862-3_15.
86. Moretti, N., Xie, X., Merino, J., Brazauskas, J., Parlikad, A. K. (2020). An openBIM approach to IoT integration with incomplete as-built data. *Applied Sciences*, 10(22), 8287.
87. Papadonikolaki, E., van Oel, C., Kagioglou, M. (2019). Organising and Managing boundaries: A structural view of collaboration with Building Information Modelling (BIM). *International Journal Of Project Management*, 37(3), 378-394.
88. Sidani, A., Dinis, F., Sanhudo, L., Duarte, J., Baptista, J., Martins, J., Soeiro, A. (2019). Recent Tools and Techniques of BIM-Based Virtual Reality: A Systematic Review. *Archives of Computational Methods in Engineering*, 28, 449-462.

89. Ghannadpour, S., RezaHoseini, A., Noori, S., Bodaghi, M. (2018). Reducing rework and increasing the civil projects quality, through Total Quality Management (TQM), by using the concept of building information modeling (BIM). *Journal of Industrial and Systems Engineering*, 12, 1-27.
90. Khalesi, H., Balali, A., Valipour, A., Antucheviciene, J., Migilinskas, D., Zigmund, V. (2020). Application of hybrid SWARA–BIM in reducing reworks of building construction projects from the perspective of time. *Sustainability*, 12(21), 8927.
91. Mehrbod, S., Staub-French, S., Mahyar, N., Tory, M. (2019). Beyond the clash: investigating BIM-based building design coordination issue representation and resolution. *Journal of information technology in construction*, 24, 33-57.
92. Zada, A. J., Tizani, W., Oti, A. H. (2014). Building information modelling (BIM)—Versioning for collaborative design. In *Computing in Civil and Building Engineering*, 512-519.
93. Bhusar, A. A., Akhare, A. R. (2014). Application of BIM in structural engineering. *SSRG International Journal of Civil Engineering*, 1(5), 12-20.
94. Mehndi, S. M., Chakraborty, I. (2020,). Simulation for a cost-effective and energy efficient retrofits of the existing building stock in India using BIM. In *International Conference On Contemporary Computing And Applications (IC3A)*, 237-243.
95. Jeong, W., Yan, W., Lee, C. J. (2020). Thermal Performance Visualization Using Object– Oriented Physical and Building Information Modeling. *Applied Sciences*, 10(17), 5888.
96. .Thede, J., Boyts, N., Teel, J., Butler, K., Bargas, E., Roth, A. (2022). Building information modeling (BIM) automation for architectural acoustics, mechanical noise calculation. *The Journal of the Acoustical Society of America*, 151(4), A56-A56.
97. Koutamanis, A. (2020). Building information modeling for construction and demolition waste minimization. In *Advances in Construction and Demolition Waste Recycling*, 101-120.
98. .Shick Alshabab, M., Vysotskiy, A., Petrichenko, M., Khalil, T. (2019). BIM-based quantity takeoff in autodesk revit and navisworks manage. In *International Scientific Conference on Energy, Environmental and Construction Engineering*, 413-421.
99. Jayasinghe, L. B., & Waldmann, D. (2020). Development of a BIM-based web tool as a material and component bank for a sustainable construction industry. *Sustainability*, 12(5), 1766.
100. Heinisuo, M., Laasonen, M., Haapio, J. (2010). BIM based manufacturing cost estimation of build-ing products. *eWork and eBusiness in Architecture, Engineering and Construction, ECPPM*, 53-59.

101. Ismail, N. A. A., Idris, N. H., Ramli, H., Sahamir, S. R., Rooshdi, R. R. R. M. (2018). Sustainable BIM-based cost estimating for quantity surveyors. *Chemical Engineering Transactions*, 63, 235-240.
102. Taihairan, R., Ismail, Z. (2015). BIM: Integrating Cost Estimates at Initial/Design Stage. *International Journal of Sustainable Construction Engineering and Technology*, 6, 62-74.
103. Baarimah, A. O., Alaloul, W. S., Liew, M. S., Al-Aidrous, A. H. M., Alawag, A. M., Musarat, M. A. (2021). Integration of building information modeling (BIM) and value engineering in construction projects: a bibliometric analysis. In *2021 Third International Sustainability and Resilience Conference: Climate Change*, 362-367.
104. Li, Y., Li, Q. (2020). The Application of BIM Technology in Budget Control of Port Construction Cost. *Journal of Coastal Research*, 103, 644 – 648.
105. Atabay, Ş., Gurgun, A., Demirbas, A. (2019). *Design Of Certified Green Buildings Using Building Information Modeling*. Proceedings of International Structural Engineering and Construction. <https://doi.org/10.14455/isec.res.2019.57>.
106. Atabay, S., Gurgun, A. P., Demirbas, A. G. (2019). Design Of Certified Green Buildings Using Building Information Modeling. *Proceedings of International Structural Engineering and Construction*, 6(1), 1-6.
107. Omayer, H. M., & Badawy, N. S. (2020). Building Information Modeling BIM as a development tool for the management of construction projects. *Fayoum University Journal of Engineering*, 3(2), 9-26.
108. Love, P. E., Edwards, D. J., Han, S. (2011). Bad apple theory of human error and building information modelling: A systemic model for BIM implementation. *28th ISARC, Seoul, Korea*, 349-54.
109. Li, H., Zhang, C., Song, S., Demirkesen, S., Chang, R. (2020). Improving tolerance control on modular construction project with 3D laser scanning and BIM: A case study of removable floodwall project. *Applied Sciences*, 10(23), 8680.
110. Li, C., Xue, F., Li, X., Hong, J., Shen, G. (2018). An Internet of Things-enabled BIM platform for on-site assembly services in prefabricated construction. *Automation in Construction*, 89, 146-161.
111. Gbadamosi, A. Q., Mahamadu, A. M., Oyedele, L. O., Akinade, O. O., Manu, P., Mahdjoubi, L., Aigbavboa, C. (2019). Offsite construction: Developing a BIM-Based optimizer for assembly. *Journal of cleaner production*, 215, 1180-1190.
112. Shen, W. (2022). Application of BIM and Internet of Things Technology in Material Management of Construction Projects. *Advances in Materials Science and Engineering*. <https://doi.org/10.1155/2022/5381252>.

113. Li, X., Wu, P., Shen, G., Wang, X., Teng, Y. (2017). Mapping the knowledge domains of Building Information Modeling (BIM): A bibliometric approach. *Automation in Construction*, 84, 195-206.
114. Wang, D. (2013). Analysis and Application of BIM Technology in the Project Goal Control. *Advanced Materials Research*, 671-674, 2978 - 2981.
115. Wu, X. (2020). Assembly Building Material Management Method Based on BIM Technology. <https://doi.org/10.21203/rs.3.rs-72285/v1>.
116. Mall, A. (2019). Reducing material waste with the application of Building Information Modelling (BIM). <https://doi.org/10.51415/10321/3253>.
117. Cao, Y., Li, Y. (2021). The Study on Design Method of Assembly Structure Based on Computer BIM Technology. *Journal of Physics: Conference Series*,
118. Cao, Y., Li, Y. (2021). The Study on Design Method of Assembly Structure Based on Computer BIM Technology. In *Journal of Physics: Conference Series* 1992(2), 022199).
119. Santos, A., Witicovski, L., Garcia, L., Scheer, S. (2009). A utilização do BIM em projetos de construção civil. *Iberoamerican Journal of Industrial Engineering*, 1, 24-42.
120. .Ding, Z., Liu, S., Liao, L., Zhang, L. (2019). A digital construction framework integrating building information modeling and reverse engineering technologies for renovation projects. *Automation in Construction*, 102, 45-58.
121. Khasbage, Y. (2022). Study On Building Information Modeling And Implementation Of Clash Detection Tool In Building Design. *Interantional Journal Of Scientific Research In Engineering And Management*. <https://doi.org/10.55041/ijrsrem14580>.
122. S, R., George, D. (2022). Relative Study on Clash Detection and its Effects on BIM Modelling. *International Journal for Research in Applied Science and Engineering Technology*. <https://doi.org/10.22214/ijraset.2022.46881>.
123. Kermanshahi, E. K., Tahir, M. B. M., Lim, N. H. A. S., Balasbaneh, A. T., Roshanghalb, S. (2020). Implementation of building information modeling for construction clash detection process in the design stage: a case study of Malaysian police headquarter building. In *IOP Conference Series: Earth and Environmental Science*, 476(1), 012009).
124. Bevanda, V., Andreea, G. (2022). Building Information Modelling (BIM) and Engineering Evolution in a Digital World. *International Scientific Conference ERAZ - Knowledge Based Sustainable Development*. <https://doi.org/10.31410/eraz.2022.153>.
125. .Jun, F., Jing, W. (2019). Application of BIM Technology in Schedule Management of Project. *Journal of Information Technologyin Civil Engineering and Architecture*, 11(6), 66-69.

126. Ansah, M. K., Chen, X., Yang, H., Lu, L., Lam, P. T. (2021). Developing an automated BIM-based life cycle assessment approach for modularly designed high-rise buildings. *Environmental Impact Assessment Review*, 90, 106618.
127. Salehi, S., Yitmen, I. (2018). Modeling and analysis of the impact of BIM-based field data capturing technologies on automated construction progress monitoring. *International Journal of Civil Engineering*, 16, 1669-1685.
128. Mutis, I., Ramachandran, A., Martínez, M. (2018). The BIMbot: A Cognitive Assistant in the BIM Room. *Advances in Informatics and Computing in Civil and Construction Engineering*. https://doi.org/10.1007/978-3-030-00220-6_19.
129. Zhang, J., Seet, B., Lie, T. (2015). Building Information Modelling for Smart Built Environments. *Buildings*, 5, 100-115.
130. Kim, M., Wang, Q., Park, J., Cheng, J., Sohn, H., Chang, C. (2016). Automated dimensional quality assurance of full-scale precast concrete elements using laser scanning and BIM. *Automation in Construction*, 72, 102-114.
131. Braun, A., Tuttas, S., Stilla, U., Borrmann, A. (2018). Bim-based progress monitoring. *Building Information Modeling: Technology Foundations and Industry Practice*, 463-476.
132. Hanko, M., Ďubek, M. (2022). Maintenance Methodology In The Facility Management System As A Basis For Bim Technology. *Czech Journal of Civil Engineering*, 8(2), 27-33.
133. Seeam, A., Zheng, T., Lu, Y., Usmani, A., Laurenson, D. (2013). BIM integrated workflow management and monitoring system for modular buildings. *International Journal of 3-D Information Modeling (IJ3DIM)*, 2(1), 17-28.
134. Chen, Z., Jiadi, L., Yu, Y., Zhou, C., Yan, R. (2017). Experimental study of an innovative modular steel building connection. *Journal of Constructional Steel Research*, 139, 69-82.
135. Wang, J. Z., Wei, G. A. (2020). Bim-Based Technology Implementation On Quality Management In Construction Engineering. In *Journal of Physics: Conference Series*, 1601 4), 042043
136. Khasbage, Y. (2022). Study On Building Information Modeling And Implementation Of Clash Detection Tool In Building Design. *Interantional Journal Of Scientific Research In Engineering And Management*. <https://doi.org/10.55041/ijsrem14580>.
137. Savitri, D. M., Pramudya, A. A. (2020). Clash detection analysis with BIM-based software on midrise building construction project. In *IOP Conference Series: Earth and Environmental Science*, 426, (1), 012002.

138. Kermanshahi, E. K., Tahir, M. B. M., Lim, N. H. A. S., Balasbaneh, A. T., Roshanghalb, S. (2020). Implementation of building information modeling for construction clash detection process in the design stage: a case study of Malaysian police headquarter building. In *IOP Conference Series: Earth and Environmental Science*, 476(1), 012009.
139. Bonenberg, W., Wei, X., Zhou, M. (2018). BIM in Prefabrication and Modular Building. *Advances in Human Factors, Sustainable Urban Planning and Infrastructure*. https://doi.org/10.1007/978-3-319-94199-8_10.
140. Cheng, M., Chang, N. (2011). Radio Frequency Identification (RFID) Integrated with Building Information Model (BIM) for Open-Building Life Cycle Information Management. 485-490.
141. Liu, H., Al-Hussein, M., Lu, M. (2015). BIM-based integrated approach for detailed construction scheduling under resource constraints. *Automation in Construction*, 53, 29-43.
142. Gao, X., Wu, Y., Li, Y. (2019). Research on information integration of construction project management based on BIM. In *IOP Conference Series: Earth and Environmental Science*, 267 (3), 032069.
143. Xu, T. (2018). Achieving Cooperative Design Based on BIM Cloud Platform. In *Cooperative Design, Visualization, and Engineering: 15th International Conference, CDVE 2018, Hangzhou, China, , Proceedings*, 15, 321-325.
144. Garrido, M. C., Mendes Jr, R., Scheer, S., Campestrini, T. F. (2015). Using BIM for last planner system: case studies in Brazil. In *Computing in Civil Engineering*, 604-611.
145. Ospina-Alvarado, A. M., Castro-Lacouture, D. (2010). Interaction of processes and phases in project scheduling using BIM for A/E/C/FM integration. In *Construction Research Congress Innovation for Reshaping Construction Practice*, 939-948.
146. Ganbat, T., Chong, H. Y., Liao, P. C. (2020). Mapping BIM uses for risk mitigation in international construction projects. *Advances in Civil Engineering*, 1-13.
147. Li, R., Zhao, H., Wang, X., Wang, Y. (2023). Research on Construction Organization Design and Engineering Cost Application Based on BIM Technology. In *Journal of Physics: Conference Series*, 2424 (1), 012034.
148. Wang, N. (2020, October). Research on Fine Management of Engineering Cost Based on BIM Technology. In *Journal of Physics: Conference Series*, 1648(2), 022193.
149. Cao, Y., Li, Y. (2021). The Study on Design Method of Assembly Structure Based on Computer BIM Technology. *Journal of Physics: Conference Series*, 2, 1992.

150. He, L., Xie, Y., Li, Y. (2022). Application and Research of Data Mining Technology Bim and Internet of Things in Engineering Construction. *Lecture Notes on Data Engineering and Communications Technologies*, 1,261-267.
151. Lv, M., Zhou, L., Wang, Y., Yang, K., Yang, C. (2022). Summary of BIM Technology Application in a Dormitory Building Project. *Advances in Transdisciplinary Engineering*,
152. Qiu, S., Xu, H., Jin, J., Zhang, H., Sun, K. (2019, December). Application of BIM technology in construction engineering. In *IOP Conference Series: Earth and Environmental Science*, 371(2) 022073).
153. Volkov, A., Chelyshkov, P., Lysenko, D. (2016). Information management in the application of BIM in construction. The roles and functions of the participants of the construction process. *Procedia Engineering*, 153, 828-832.
154. Wang, M., Qian, Y., Yuan, R., Wang, Q. (2019). Visual Analysis on Evolution, Hotspots and Frontier of International BIM Research -Literature Metrology Based on Web of Science Database [Article]. *Tiedao Xuebao/Journal of the China Railway Society*, 41(6), 9-15.
155. Zhang, L., Liu, H. (2021). Research on application strategy of BIM technology in construction project management. In *E3S Web of Conferences*, 236, 05002.
156. Isikdag, U., (2015). The future of building information modelling: BIM 2.0. *Enhanced building information models: using IoT services and integration patterns*, 13-24.
157. Borrmann, A., König, M., Koch, C., Beetz, J. (2018). *Building information modeling: Why? what? how?* , Springer International Publishing, 1-24.
158. Svalestuen, F., Knotten, V., Lædre, O., Drevland, F., Lohne, J. (2017). Using Building Information Model (Bim) Devices To Improve Information Flow And Collaboration On Construction Sites [Article]. *Journal of Information Technology in Construction*, 22, 204-219. <https://www.scopus.com/inward/record.uri?eid=2-s2.0-85030857664partnerID=40md5=fafecce0182ce9cd7a7f0e9b543ab7da>
159. Heng, L. I., Hong-yu, L. I. (2020). Applications of BIM in Construction Engineering in China: A Review. In *E3S Web of Conferences*, 143, 01007.
160. Eadie, R., Browne, M., Odeyinka, H., McKeown, C., McNiff, S. (2013). BIM implementation throughout the UK construction project lifecycle: An analysis. *Automation in construction*, 36, 145-151.
161. Oraee, M., Hosseini, M. R., Edwards, D., Papadonikolaki, E. (2022). Collaboration in BIM-based construction networks: a qualitative model of influential factors. *Engineering, Construction and Architectural Management*, 29(3), 1194-1217.

162. Oraee, M., Hosseini, M. R., Papadonikolaki, E., Palliyaguru, R., Arashpour, M. (2017). Collaboration in BIM-based construction networks: A bibliometric-qualitative literature review [Article]. *International Journal of Project Management*, 35(7), 1288-1301.
163. Ding, C. (2023). Construction Management Mode of Building Engineering Based on BIM Technology. Lecture Notes on Data Engineering and Communications Technologies,
164. Mo, L. (2018). Research on Application of BIM Technology in Construction Project Cost Management. Proceedings - 2018 3rd International Conference on Smart City and Systems Engineering, ICSCSE 208-210.
165. Wen, Z. (2019). Application Research of BIM Technology in Engineering Cost Management. In *IOP Conference Series: Earth and Environmental Science*, 295 (4), 042037.



Gazili olmak ayrıcalıktır